

PAVEMENT SCHEDULE

LOCATION	BIT MATL PR CT (GALLON)	AGGREGATE (PRIME COAT) (TON)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 N90, (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90, (TON)
13TH STREET				
STA. 10+50.46 TO STA. 16+00.00	160.4	4.6	160.4	160.4
STA. 16+85.36 TO STA. 23+06.82	168.8	4.8	168.8	168.8
ELIZABETH AVENUE				
STA. 100+18.23 TO STA. 113+41.21	357.2	8.8	357.2	357.2
McCAMBRIDGE AVENUE				
STA. 200+51.12 TO STA. 212+98.43	1098.9	8.8	492.3	492.3
STA. 212+98.43 TO STA. 215+79.14	70.0	2.0	70.0	70.0
<b>TOTAL</b>	<b>1855</b>	<b>29</b>	<b>1249</b>	<b>1249</b>

PAVEMENT PATCHING SCHEDULE

LOCATION	SIZE		PAVEMENT PATCHING CLASS C PATCHES		
	LENGTH	WIDTH	TYPE II	TYPE III	TYPE IV
	(FOOT)	(FOOT)	10" (SQ YD)	10" (SQ YD)	10" (SQ YD)
13TH STREET					
STA. 13+44.89 - 19.13' RT TO STA. 13+58.45 - 12.50' RT		IRREGULAR	8.9		
STA. 13+49.14 - 0.00' LT TO STA. 13+59.14 - 0.00' LT	10	X 20.1 avg		21.5	
STA. 13+87.29 - 0.00' LT TO STA. 14+42.29 - 0.00' LT	55	X  8			48.9
ELIZABETH AVENUE					
STA. 100+18.71 - 2.00' LT TO STA. 100+48.75 - 2.00' LT		IRREGULAR			68.4
STA. 102+54.25 - 2.00' RT TO STA. 102+71.25 - 2.00' RT	17	X  9		17	
STA. 102+99.37 - 10.00' LT TO STA. 103+15.37 - 10.00' LT	16	X  6	10.6		
STA. 104+92.36 - 6.00' RT TO STA. 105+68.36 - 1.00' RT		IRREGULAR			100.7
STA. 106+03.52 - 11.00' LT TO STA. 106+19.02 - 11.00' LT		IRREGULAR	12.7		
STA. 106+04.30 - 15.00' RT TO STA. 106+16.80 - 15.00' RT		IRREGULAR	5.8		
STA. 106+35.10 TO STA. 106+45.10	10	X  16		17.8	
STA. 109+31.84 - 15.92' RT TO STA. 109+63.21 - 15.97' RT		IRREGULAR			69.2
STA. 109+63.21 - 15.97' RT TO STA. 109+95.35 - 16.02' RT		IRREGULAR			38.1
STA. 111+41.61 - 10.00' RT TO STA. 111+70.61 - 10.00' RT	29	X  6.2		19.7	
STA. 111+79.35 - 10.00' LT TO STA. 112+49.35 - 10.00' LT	70	X  6			47
STA. 112+00.35 TO STA. 112+17.35	17	X  14			26.4
STA. 112+84.16 TO STA. 112+99.16	15	X  18			30
STA. 113+15.54 - 5.50' RT TO STA. 113+41.23 - 1.00' RT		IRREGULAR			47.3
McCAMBRIDGE AVENUE					
STA. 201+51.12 LT TO STA. 201+64.50 LT	13.4	X  16.3		24.3	
STA. 202+93.07 - 2.00' LT TO STA. 204+51.77 - 2.00' LT		IRREGULAR			215.7
STA. 204+80.25 - 9.00' RT TO STA. 204+87.25 - 9.00' RT	7	X  16	12.4		
STA. 205+26.55 - 6.00' LT TO STA. 205+67.28 - 6.00' LT	40.7	X  9.9			45.1
STA. 205+26.55 TO STA. 205+67.28	40.7	X  10			45.1
STA. 205+26.55 - 4.00' RT TO STA. 205+99.57 - 4.00' RT		IRREGULAR			81.3
STA. 206+03.65 TO STA. 206+47.07	7.5	X  43.4			36.2
STA. 206+03.65 - 5.00' LT TO STA. 206+29.34 - 5.00' LT	25.7	X  6		17.1	
STA. 206+67.78 - 5.00' LT TO STA. 206+93.94 - 5.00' LT	26.2	X  6		17.4	
STA. 209+39.06 - 6.00' RT TO STA. 210+19.66 - 6.00' RT	80.6	X  10.5			94
STA. 212+23.30 - 6.00' LT TO STA. 212+43.05 - 6.00' LT	33.5	X  10.4			38.5
STA. 212+72.95 - 18.08' RT TO STA. 212+91.93 - 14.00' RT		IRREGULAR			31
STA. 212+91.93 - 6.00' LT TO STA. 212+98.43 - 6.00' LRT	6.5	X  10.3	7.5		
STA. 212+91.93 TO STA. 212+98.43	6.5	X  12	8.7		
STA. 212+91.93 - 6.00' RT TO STA. 212+98.43 - 6.00' RT	6.5	X  10	7.2		
STA. 212+91.93 - 16.00' RT TO STA. 213+02.42 - 16.00' RT	10.5	X  14		16.3	
<b>TOTAL</b>			<b>74</b>	<b>151</b>	<b>1063</b>

COMBINATION CURB AND GUTTER SCHEDULE

LOCATION	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)	CONCRETE CURB, TYPE B (FOOT)
13TH STREET		
STA. 10+74.17 - 20.01' LT TO STA. 10+93.17 - 19.91' LT	19.00	
STA. 13+01.54 - 19.88' RT TO STA. 13+13.81 - 29.06' RT	16.07	
STA. 13+01.68 - 19.95' LT TO STA. 13+13.09 - 27.52' LT	14.22	
STA. 13+45.63 - 28.66' RT TO STA. 13+57.28 - 20.14' RT	15.08	
STA. 13+46.90 - 27.72' LT TO STA. 13+57.24 - 19.96' LT	13.54	
STA. 17+05.85 - 19.37' LT TO STA. 17+25.16 - 17.94' LT	19.37	
STA. 19+66.91 - 17.98' RT TO STA. 19+76.41 - 27.87' RT	14.64	
STA. 19+67.08 - 18.81' LT TO STA. 19+76.64 - 30.31' LT	15.66	
STA. 20+13.19 - 27.87' RT TO STA. 20+22.54 - 18.34' RT	13.03	
STA. 20+13.02 - 30.42' LT TO STA. 20+22.44 - 18.82' LT	13.67	
STA. 22+96.22 - 19.25' RT TO STA. 23+01.47 - 22.39' RT	6.17	
STA. 22+96.45 - 18.52' LT TO STA. 23+01.59 - 21.41' LT	5.94	
ELIZABETH AVENUE		
STA. 101+87.14 - 25.22' RT TO STA. 101+90.91 - 42.08' RT	17.35	
STA. 102+24.82 - 31.07' RT TO STA. 102+24.82 - 36.16' RT	5.10	
STA. 102+99.63 - 17.90' RT TO STA. 103+26.68 - 17.78' RT	27.04	
STA. 105+66.11 - 27.72' LT TO STA. 105+67.23 - 32.81' LT	5.28	
STA. 105+67.71 - 27.11' RT TO STA. 105+69.00 - 32.10' RT	5.16	
STA. 106+02.84 - 32.88' LT TO STA. 106+03.90 - 27.64' LT	5.41	
STA. 106+05.07 - 32.23' RT TO STA. 106+06.05 - 27.07' RT	5.30	
STA. 106+16.13 - 18.45' RT TO STA. 106+21.32 - 17.91' RT	5.24	
STA. 106+16.23 - 18.13' LT TO STA. 106+21.32 - 17.84' LT	5.11	
STA. 109+43.44 - 26.88' RT TO STA. 109+44.56 - 32.12' RT	5.39	
STA. 109+80.61 - 32.09' RT TO STA. 109+81.93 - 26.88' RT	5.41	
STA. 110+57.89 - 17.96' RT TO STA. 111+26.09 - 18.03' RT	68.20	
STA. 113+26.08 - 18.12' LT TO STA. 113+31.43 - 20.12' LT	5.75	
STA. 113+26.12 - 17.82' RT TO STA. 113+36.19 - 22.49' RT	11.38	
McCAMBRIDGE AVENUE		
STA. 204+33.36 - 17.79' RT TO STA. 204+38.36 - 17.83' RT	5.00	
STA. 204+33.49 - 18.30' LT TO STA. 204+45.98 - 28.85' LT	17.39	
STA. 204+50.50 - 21.02' RT TO STA. 204+54.08 - 25.35' RT	5.71	
STA. 204+79.70 - 28.77' LT TO STA. 204+82.22 - 23.50' LT	5.87	
STA. 204+94.33 - 25.65' RT TO STA. 204+97.96 - 21.05' RT	5.90	
STA. 209+91.54 - 22.05' LT TO STA. 209+95.86 - 38.49' LT	17.65	
STA. 210+28.06 - 38.12' LT TO STA. 210+32.20 - 22.11' LT	17.14	
STA. 212+64.75 - 17.63' RT TO STA. 112+84.89 - 42.39' RT		36.60
STA. 213+10.74 - 42.99' RT TO STA. 213+27.68 - 17.54' RT		36.40
STA. 215+21.38 - 21.68' LT TO STA. 215+26.77 - 38.03' LT	17.93	
STA. 215+62.42 - 37.23' LT TO STA. 215+68.83 - 20.91' LT	18.37	
<b>TOTAL</b>	<b>454</b>	<b>73</b>

DRIVEWAY PAVEMENT SCHEDULE

LOCATION	PCC DRIVEWAY PAVEMENT 8 INCH (SQ YD)
13TH STREET	
STA. 14+76.73 - 20.54' RT TO STA. 14+93.37 - 20.55' RT	13.9
<b>TOTAL</b>	<b>14</b>

FILE NAME = combsched1es13th.dgn

USER NAME = joromy	DESIGNED - SAS	REVISED -
PLOT SCALE = #SCALE#	DRAWN - JJB	REVISED -
PLOT DATE = 3/29/2012	CHECKED - BFK	REVISED -
	DATE - 03/13/12	REVISED -

**CITY OF MADISON**  
**13TH STREET, ELIZABETH AVENUE,**  
**AND McCAMBRIDGE AVENUE REHABILITATION**

QUANTITY SCHEDULES	
SCALE: N.T.S.	SHEET NO. 1 OF 4 SHEETS
STA.	TO STA.

F.A.U. RTE. 9101	SECTION 09-00057-00-PV	COUNTY MADISON	TOTAL SHEETS 58	SHEET NO. 12
CONTRACT NO. 97489				
[ILLINOIS] FED. AID PROJECT				