

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 9562	10-00087-00-PV	SALINE	36	4
MISSOURI STREET		HARRISBURG		
PROJECT TCSP-IL10(101)		JOB C-99-545-10		

PCC PAVEMENT SCHEDULE				
LOCATION	PORTLAND CEMENT CONCRETE PAVEMENT 7" (SQ YD)	SUBBASE GRANULAR MATERIAL, TYPE A (TON)	AGGREGATE SHOULDERS, TYPE A 4" (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (FOOT)
MISSOURI STREET				
STA 0+43.84 LT TO STA 4+59.20 LT				426
STA 0+44.53 TO STA 24+06.54	6414	1585		
STA 0+46.51 RT TO STA 4+48.00 RT			273	
STA 4+71.20 LT TO STA 7+92.26 LT				352
STA 4+84.00 RT TO STA 7+81.73 RT			196	
STA 8+01.34 RT TO STA 8+89.09 RT			54	
STA 8+06.01 LT TO STA 23+07.19 LT				1523
STA 9+15.56 RT TO STA 10+27.11 RT			70	
STA 10+49.11 RT TO STA 11+79.05 RT			81	
STA 12+49.36 RT TO STA 13+83.26 RT			84	
STA 14+41.04 RT TO STA 23+97.02 RT			652	
STA 23+07.19 LT TO STA 23+96.85 LT			71	
STA 23+96.85 LT TO STA 24+05.37 LT (IL RTE 13 SHLD)	22			
STA 23+97.02 RT TO STA 24+05.70 RT (IL RTE 13 SHLD)	32			
TOTALS	6468	1585	1481	2301

TEMPORARY EROSION CONTROL SCHEDULE			
LOCATION	PERIMETER EROSION BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)	TEMPORARY DITCH CHECKS (FOOT)
MISSOURI STREET			
STA 0+75 RT TO STA 4+50 RT	375		
STA 1+15 LT		1	
STA 3+65 LT		1	
STA 4+90 LT		1	
STA 5+00 RT TO STA 7+20 RT (3 @ 10' EACH)			30
STA 5+80 LT		1	
STA 7+00 LT		1	
STA 8+10 RT TO STA 10+20 RT (5 @ 10' EACH)			50
STA 8+87.74 RT		1	
STA 9+50 LT		1	
STA 10+22.14 RT		1	
STA 10+50 RT TO STA 11+50 RT	100		
STA 10+85 LT		1	
STA 11+27 LT		1	
STA 11+42 LT		1	
STA 11+75 LT		1	
STA 11+90.17 RT		1	
STA 12+70 RT TO STA 18+50 RT (4 @ 10' EACH)			40
STA 13+30 LT		1	
STA 13+63.26 RT		1	
STA 14+95 LT		1	
STA 16+70 LT		1	
STA 18+50 RT TO STA 24+00 RT	550		
STA 19+05 LT		1	
STA 21+55 LT		1	
TOTALS	1025	19	120

PAVEMENT MARKING SCHEDULE		
LOCATION	PAINT PAVEMENT MARKING - LINE 4" (FOOT)	PAINT PAVEMENT MARKING - LINE 12" (FOOT)
STA 0+44.53 TO STA 24+06.54 (SKIP DASH)	590	
STA 0+44.53 RT TO STA 24+06.54 RT (EDGE LINE)	2432	
STA 23+07.19 LT TO STA 24+06.54 LT (EDGE LINE)	139	
STA 0+70 LT (STOP BAR)		11
STA 4+60 LT (NATIONAL STREET STOP BAR)		6
STA 7+95 LT (SHORT STREET STOP BAR)		7
STA 23+65 RT (STOP BAR)		30
TOTALS	3161	54

RIPRAP SCHEDULE	
LOCATION	STONE RIPRAP, CLASS A3 (TON)
MISSOURI STREET	
STA 5+06.56 RT	4.0
STA 5+80.00 RT	4.0
STA 7+18.84 RT	4.0
STA 11+73.90 RT	4.0
STA 13+30.00 RT	3.3
STA 14+95.00 RT	3.3
STA 16+70.00 RT	3.3
STA 19+05.00 RT	3.3
STA 21+55.00 RT	3.3
TOTALS	33

REMOVAL SCHEDULE		
LOCATION	PIPE CULVERT REMOVAL (FOOT)	TRENCH BACKFILL (CU YD)
MISSOURI STREET		
STA 1+16 LT TO STA 1+57 LT	42	3.6
STA 4+19 LT TO STA 5+07 RT	101	14.0
STA 5+45 LT TO STA 5+76 RT	53	9.1
STA 7+75 RT TO STA 8+15 RT	40	3.0
STA 10+28 RT TO STA 10+48 RT	20	2.7
STA 11+85 RT TO STA 12+25 RT	40	5.4
STA 14+05 RT TO STA 14+34 RT	30	
STA 15+54 RT	33	
STA 16+14 RT TO STA 16+45 RT	31	
STA 17+35 RT	33	
TOTALS	423	38

NOTE:
DRIVEWAY PAVEMENT REMOVAL IS SHOWN ON
DRIVEWAY ENTRANCE DETAIL SHEET.