

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 6 of 89
Contract Number 44904

PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 1	DISTRICT 2	DISTRICT 3	DISTRICT 4	DISTRICT 5	DISTRICT 7
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	14.00		4.00	5.00	1.00	3.00	1.00
REMOVE LUMINAIRE	EACH	5.00		5.00				
RELOCATE ELECTRIC SERVICE	EACH	8.00		3.00		1.00	3.00	1.00
PAINT OVERHEAD SIGN SUPPORT	EACH	5.00				5.00		
CONCRETE REMOVAL SPECIAL	SQ YD	108.40					108.40	
IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	2.00					2.00	
MOBILIZATION	L SUM	1.00	0.15	0.18	0.24	0.12	0.20	0.11
TRAFFIC CONTROL & PROTECTION	L SUM	1.00	0.30	0.10	0.20	0.10	0.20	0.10
REMOVE SIGN PANEL - TYPE 1	SQ FT	82.00						82.00
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A (4' - 0 X 4' - 6")	FOOT	434.33		134.00			300.33	
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A (4' - 6" X 5' - 3")	FOOT	588.00			588.00			
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36" X 5' - 6")	FOOT	30.00						30.00
OVERHEAD SIGN STRUCTURE WALKWAY (SPECIAL)	FOOT	88.00		68.00			20.00	
DRILL SHAFT CONCRETE FOUNDATIONS	CU YD	127.70		53.90		21.50	45.10	7.20
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	11.00		2.00	5.00		4.00	
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	4.00						4.00
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	20.00		8.00		2.00	6.00	4.00