

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 17 of 89
Contract Number 44904

District 2
Schedule of Locations for Overhead Sign Structure Replacement

Location No.:	2-01	State I.D. No.:	2S006I080R059.9				
County:	Bureau	Route:	I - 80	M.P.:	59.9	Direction:	EB
Description of Work		Unit	Quantity				
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00				
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	1.00				
FURNISH & INSTALL SADDLE SHIM BLOCK		EACH	4.00				
FURNISH & INSTALL INTERNAL TRUSS DAMPER		EACH	1.00				
REPLACE / TIGHTEN CLIPS PER SIGN		EACH	2.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
DRILLED SHAFT CONCRETE FOUNDATIONS		CU YD	21.50				
REMOVE CONCRETE FOUNDATION - OVERHEAD		EACH	2.00				
RELOCATE ELECTRIC SERVICE		EACH	1.00				
OVERHEAD SIGN STRUCTURE WALKWAY		FOOT	88.00				
OVERHEAD SIGN STRUCTURE WALKWAY, SPECIAL		FOOT	30.00				
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00				
REMOVE EXISTING LUMINAIRE		EACH	2.00				

Location No.:	2-04	State I.D. No.:	2S050I080R073.4				
County:	LaSalle	Route:	I - 80	M.P.:	73.4	Direction:	EB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00				
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00				
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A		FOOT	84.00				
REMOVE & REINSTALL WALKWAY		FOOT	29.50				
REMOVE & REINSTALL SIGN PANEL		SQ FT	268.00				
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	20.40				
REMOVE CONCRETE FOUNDATION OVERHEAD		EACH	2.00				
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	4.00				
RELOCATE ELECTRIC SERVICE		EACH	1.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00				

Location No.:	2-02	State I.D. No.:	2S037I080L010.2				
County:	Henry	Route:	I - 80	M.P.:	10.2	Direction:	WB
Description of Work		Unit	Quantity				
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00				
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00				
FURNISH & INSTALL SADDLE SHIM BLOCK		EACH	4.00				
FURNISH & INSTALL INTERNAL TRUSS DAMPER		EACH	1.00				
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00				
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00				
REPLACE U-BOLT		EACH	4.00				
REPLACE HANDRAIL SUPPORT		EACH	2.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
REPLACE OVERHEAD SIGN WALKWAY		FOOT	20.00				
OVERHEAD SIGN STRUCTURE WALKWAY		FOOT	74.00				

Location No.:	2-03	State I.D. No.:	2S037I080L011.4				
County:	Henry	Route:	I - 80	M.P.:	11.4	Direction:	WB
Description of Work		Unit	Quantity				
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00				
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00				
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A		FOOT	50.00				
DRILLED SHAFT CONCRETE FOUNDATIONS		CU YD	12.00				
REMOVE CONCRETE FOUNDATION - OVERHEAD		EACH	4.00				
REMOVE & REINSTALL SIGN PANEL		SQ FT	432.00				
DISCONNECT / RECONNECT ELECTRIC SERVICE		EACH	1.00				
RELOCATE ELECTRIC SERVICE		EACH	1.00				
OVERHEAD SIGN STRUCTURE WALKWAY, SPECIAL		FOOT	38.00				
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00				
REMOVE EXISTING LUMINAIRE		EACH	3.00				