

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	2004-025 RS	LAKE	116	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
• PARK ROADS		IDNR File No. 2-03-025	091-191-04	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY I000	JUNCTION CHAMBER Y007	LIGHTING Y030-1E	
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	3000			3000	
X0325225	BRICK PAVERS REMOVE AND REINSTALL	SQ FT	50	50			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	134	134			
20200100	EARTH EXCAVATION	CU YD	8378	8378			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	30.2	30.2			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6633	6633			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	120	120			
20800150	TRENCH BACKFILL	CU YD	148	90	58		
20900330	GRANULAR BACKFILL	TON	137		137		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	16828	16807	21		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	352	352			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	352	352			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	352	352			
* 25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	3.93	3.91	0.02		
* 25200200	SUPPLEMENTAL WATERING	UNIT	189	189			
28000400	PERIMETER EROSION BARRIER	FOOT	8420	8420			
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	12	12			
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	868	868			
31102000	SUB-BASE GRANULAR MATERIAL, TYPE C	CU YD	20	20			
35500100	BITUMINOUS BASE COURSE 4"	SQ YD	202	202			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23			
40600300	AGGREGATE (PRIME COAT)	TON	113	113			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1888	1888			
42101300	PROTECTIVE COAT	SQ YD	770	770			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5080	5080			
42400800	DETECTABLE WARNINGS	SQ FT	345	345			
44000100	PAVEMENT REMOVAL	SQ YD	9429	9408	21		

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY I000	JUNCTION CHAMBER Y007	LIGHTING Y030-1E	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	210	210			
44000600	SIDEWALK REMOVAL	SQ FT	5080	5080			
44004250	PAVED SHOULDER REMOVAL	SQ YD	196	196			
44213200	SAW CUTS	FOOT	135	75		60	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	180	180			
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	235	235			
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	505	505			
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1		
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	30	30			
50200100	STRUCTURE EXCAVATION	CU YD	31		31		
50300225	CONCRETE STRUCTURES	CU YD	28		28		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2620		2620		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2			
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1			
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1	1			
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	63	63			
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	143	143			
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	130	130			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	444	444			
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	16		16		
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	468	452	16		
55101600	STORM SEWER REMOVAL 36"	FOOT	4		4		
55101800	STORM SEWER REMOVAL 42"	FOOT	3		3		
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1			
* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1	1			
60200105	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3			
60200205	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60201340	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5	5			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
NORTH POINT MARINA

Rev. 2-28-06

PLOT DATE: 1/24/2006

1/24/2006 10:40:30 AM