

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
305	1920.01-I	COOK	12	4

CONTRACT 62772

SUMMARY OF QUANTITIES

CODE NUMBER	DESCRIPTION	UNIT	TOTAL	URBAN 100% STATE
				CONSTRUCTION TYPE CODE SFTY-2A (SN 016-0533) COOK CO.
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ. YD.	1727	1727
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ. FT.	234	234
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ. YD.	1727	1727
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, 701601	L SUM	1	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1310	1310
* 78100105	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	EACH	16	16
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ. FT.	48	48
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	145	145
Z0001700	APPROACH SLAB REPAIR (FULL DEPTH)	SQ. YD.	23	23
Z0047300	PROTECTIVE SHIELD	SQ. YD	812	812
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ. YD.	3	3
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ. YD.	90	90
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ. YD.	330	330

* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES