F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3520	2005-001 RS	COOK	37	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. 62903

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000	BRIDGE SFTY-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7					
40600300	AGGREGATE (PRIME COAT)	TON	35	35					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	150	150					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	270	270					
42001300	PROTECTIVE COAT	SQ YD	2405	540	1865				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	4500	4500					
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	1580	1580					
44000900	BITUMINOUS CONCRETE REMOVAL	SQ YD	585		585				
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	1865		1865				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250					
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	700	700					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	550	550					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	175	175					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	400	400					
50300260	BRIDGE DECK GROOVING	SQ YD	1794		1794				
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	24		24				
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	970		970				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6990		6990				
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	24		24				
55039700	STORM SEWERS TO BE CLEANED	FOOT	456	456					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2					
60260100	INLETS TO BE ADJUSTED	EACH	6	6					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	7	7					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3					

✳ SPECIALITY ITEM

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: ROADWAY 1000	BRIDGE SFTY-2A				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3700	3700					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	175	175					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8000	8000					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1230	1230					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	70	70					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	170	170					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	250	250					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5410	5410					
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	715		715				
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	715		715				
✳78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140	140					
✳78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7200	7200					
✳78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1120	1120					
✳78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	70	70					
✳78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120					

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.U. 3520: GROSS POINT ROAD
SUMMARY OF QUANTITIES

PLOT DATE: 3/23/2006

3/23/2006