

* FAI 80 & 74
 ** (37-5HB-2 & 81-1HB)M
 *** Henry & Rock Island Counties

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	13	2
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

GENERAL NOTES

Paycode	Abbreviation	Units	Total Quantity	Structure No. 037-0116	Structure No. 081-0115
			100% State	HENRY CO.	ROCKISLAND CO.
			SFTY-2A		URBAN
2070220	POROUS GRANULAR EMBANKMENT	CU YD	20	20	
2070400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	54		54
50102400	CONCRETE REMOVAL	CU YD	16	3.2	12.8
5020100	STRUCTURE EXCAVATION	CU YD	74	20	54
50300130	PREFORMED JOINT SEAL 4"	FOOT	32		32
5030225	CONCRETE STRUCTURES	CU YD	12.9	2.7	10.2
5030255	CONCRETE SUPERSTRUCTURE	CU YD	0.5	0.5	
5030320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10	10	
5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1970	1550	420
5050715	JACK AND REMOVE EXISTING BEARINGS	EACH	10	10	
5080205	REINFORCEMENT BARS, EPOXY COATED	POUND	990	240	750
5910100	GEOCOMPOSITE WALL DRAIN	SQ YD	32		32
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	54	20	34
60611600	COMBINATION CONCRETE CURB AND GUTTER; (SPECIAL)	FOOT	40		40
6710100	MOBILIZATION	L SUM	1	0.5	0.5
X0301424	SILICONE JOINT SEALER	FOOT	31		31
Z001500	APPROACH SLAB REMOVAL & REPLACEMENT	SQ YD	54		54
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	0.5	0.5

The final top 100 mm (four inches) of soil in any right-of-way area disturbed by the Contractor must be capable of supporting vegetation. The soil must be from the A horizon (zero to 2³/₂ deep) of soil profiles of local soils.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 6 (modified) shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1 (modified). Class 6 (modified) shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Cubic Yard for STRUCTURE EXCAVATION.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of EARTH EXCAVATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the STRUCTURE EXCAVATION.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800 892 0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

HENRY COUNTY LOCATION

Geneseo Telephone Company
 Ameren IP
 Mediacom

ROCK ISLAND COUNTY LOCATION

SBC/Ameritech Telephone Co
 MidAmerican Energy
 McLeod USA
 City of Moline
 Kone, Inc

Summary of Quantities & General Notes
 FAI Route 80 (I-80) & FAI Route 74 (I-74)
 Section (37-5-2 & 81-1HB)M
 Henry & Rock Island Counties
 Structure No.'s 037-0116 & 081-0115