

COMPANY NAME: #COMPANY NAME#
 PROJECT CONTACT: #PROJECT CONTACT#
 CLIENT: #CLIENT#
 DATE: #DATE#
 TIME: #TIME#
 FILES

PROFILE SURVEYED PLOTTED CHECKED DATE
 NOTE BOOK PLAN NOTED DATE
 NO. STRUCTURE NOTATIONS CHG'D

PLAN SURVEYED PLOTTED CHECKED DATE
 NOTE BOOK PLAN NOTED DATE
 NO. CAD FILE NAME

80% PLOTTED
 20% STAMPED

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	1000-2A	SFTY-2A
54214923	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH. EQUIVALENT ROUND-SIZE 18"	EACH	6	6	
54214941	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ARCH. EQUIVALENT ROUND-SIZE 36"	EACH	8	8	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2	
54248160	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36"	EACH	8	8	
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	771	771	
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	500	500	
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	698	698	
550A0120	STORM SEWERS, CLASS A, TYPE 1, 24"	FOOT	108	108	
60218400	MANHOLES, TYPE A, 4-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7	
60220230	MANHOLES, TYPE A, 4-DIAMETER, SPECIAL FRAME AND GRATE	EACH	6	6	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2	
60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	12	12	
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1	
60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	10	10	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60500050	REMOVING CATCH BASINS	EACH	2	2	
60500060	REMOVING INLETS	EACH	2	2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-G-24	FOOT	6858	6858	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	60	60	
61139800	STORM SEWERS, SPECIAL 4"	FOOT	600	600	
61139900	STORM SEWERS, SPECIAL 6"	FOOT	600	600	
61140000	STORM SEWERS, SPECIAL 8"	FOOT	600	600	
61140100	STORM SEWERS, SPECIAL 10"	FOOT	600	600	
61140200	STORM SEWERS, SPECIAL 12"	FOOT	600	600	
63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100	100	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	2	2	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1	1	
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	163	163	
66400200	NON-SPECIAL WASTE DISPOSAL	CUYD	42	42	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	166	166	
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	44	44	
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10686	10686	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36	36	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	243843	243843	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	24060	24060	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	258	258	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	32430	32430	
72000100	SIGN PANEL - TYPE 1	SQ FT	372	372	
72000200	SIGN PANEL - TYPE 2	SQ FT	10	10	
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	3	3	
72500100	OBJECT MARKER - TYPE 1	EACH	2	2	
73000100	WOOD SIGN SUPPORT	FOOT	1010	1010	
73502000	RELOCATE GROUND MOUNTED SIGN SUPPORT	EACH	16	16	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36	36	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	81281	81281	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8020	8020	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	156	156	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	281	281	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	437	437	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	450	450	
X3550215	BITUMINOUS BASE COURSE SUPERPAVE 5 3/4"	SQ YD	4921	4921	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	2266	2266	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	9862	9854	8.0
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	621	621	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	8274	8268	6.0
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4-24	FOOT	154	154	
Z0000980	AGGREGATE FOR TEMPORARY ACCESS	TON	2829	2829	
Z0064225	SEALING ABANDONED WATER WELLS	EACH	1	1	
X0325321	PRECAST CONCRETE BOX CULVERT 6' X 2.5'	FOOT	54.0	54.0	
X0325331	PRECAST CONCRETE BOX CULVERT 8' X 3.5'	FOOT	54.0	54.0	

* SPECIALTY ITEM

F.A.S. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517 (2)RS-3 (3)RS-4	MCLEAN	223	5
STA.	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

66383

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.S. 1517 (U.S. ROUTE 150)
 SUMMARY OF QUANTITIES
 (SHEET 2 OF 2)

SCALE: VERT. DATE
 HORIZ. DATE

DRAWN BY
 CHECKED BY