

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	(22)N & TS-3	MARSHALL	21	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANTITY	I000-1A	Y030-1E	Y031-1F
				ROADWAY 90% FED 10% STATE	LIGHTING 100% CITY	TRAFFIC SIGNALS 90% FED 10% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10	10		
20200100	EARTH EXCAVATION	CU YD	64	64		
20800150	TRENCH BACKFILL	CU YD	4	4		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4		
25200110	SODDING, SALT TOLERANT	SQ YD	329	329		
25200200	SUPPLEMENTAL WATERING	UNIT	5	5		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	18	18		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	328	328		
40600300	AGGREGATE (PRIME COAT)	TON	9	9		
40600990	TEMPORARY RAMP	SQ YD	70	70		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	180	180		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2062	2062		
42400800	DETECTABLE WARNINGS	SQ FT	80	80		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	192	192		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	728	728		
44000600	SIDEWALK REMOVAL	SQ FT	2348	2348		
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	4099	4099		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	26	26		
56109210	WATER VALVES TO BE ADJUSTED	EACH	1	1		
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	2	2		
60500060	REMOVING INLETS	EACH	2	2		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	698	698		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	10	10		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	315	315		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1730	1730		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	474	474		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	876	876		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	91	91		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	36	36		
72000100	SIGN PANEL - TYPE 1	SQ FT	4.5	4.5		
72000200	SIGN PANEL - TYPE 2	SQ FT	40			40
72900100	METAL POST - TYPE A	FOOT	37.5	37.5		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1730	1730		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	474	474		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	876	876		

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY