CONTRACT NO. 66611

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	(2ZIN & TS-3	MARSHALL	21	4
STA.		TO STA.		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE: I000-1A ROADWAY 90%FED 10% STATE	Y030-1E LIGHTING 100% CITY	Y031-1F TRAFFIC SIGNALS 90%FED 10%STATE
* 78000650	THERMOPLASTIC PAVEMENT MARK - LINE 24"	FOOT	91	91		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20		
78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	10	10		
80500205	SERVICE INSTALLATION, TYPE B (MODIFIED)	EACH	1			1
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	557			557
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	74			74
81012900	CONDUIT IN TRENCH, 3-1/2" DIA., PVC	FOOT	17			17
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	195			195
81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	150			150
81021360	CONDUIT PUSHED, 3-1/2" DIA., PVC	FOOT	62			62
81400400	CONCRETE HANDHOLE	EACH	5			5
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1			1
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	646			646
81702130	ELECTRIC CABLE IN CONDUIT, 600 (XLP TYPE USE) 1/C NO 6	FOOT	1,872			1,872
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2		2	
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1		1	
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET,SPECIAL	EACH	1			1
86000100	MASTER CONTROLLER	EACH	1			1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1794			1794
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	548			548
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	973			973
87601200	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE II	EACH	2			2
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1			1
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1			1
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1			1
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1			1
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	46			46
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	8			8

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

JANUARY 13, 2006
J:\HQD\DGN\Sheet 0118.dgn