

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-2HB)I-1	LASALLE	26	4
ILLINOIS			STATE PROJECT	

LOCATION	BITUMINOUS CONCRETE REMOVAL (DECK)	WATERPROOFING MEMBRANE SYSTEM	BITUMINOUS CONCRETE SURFACE CSE. SUPERPAVE MIX "D", N70
	SQ YD	SQ YD	TON
STAGE I - DECK	374	340	29
STAGE II - DECK	306	340	29
TOTAL	680	680	58

LOCATION	CONCRETE REMOVAL	CONCRETE SUPERSTRUCTURE
	CU YD	CU YD
STAGE I - PARAPET	0.95	0.95
STAGE II - PARAPET	0.95	0.95
TOTAL	1.90	1.90

LOCATION	BRIDGE HANDRAIL REMOVAL
	STAGE I - PARAPET
STAGE II - PARAPET	204
TOTAL	408

LOCATION	SILICONE JOINT SEALER 1.5"
	FOOT
STAGE I - DECK	38
STAGE II - DECK	38
TOTAL	75

LOCATION	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	WORKZONE PAVEMENT MARKING REMOVAL
	SQ FT	FOOT	SQ FT
STAGE I	1611	3694	1219
STAGE II	1650	3831	1264
TOTAL	3261	7525	2483

LOCATION	THERMOPLASTIC PAVEMENT MARKING L & S	THERMOPLASTIC PAVEMENT MARKING LINE 4"		THERMOPLASTIC PAVEMENT MARKING LINE 6"	THERMOPLASTIC PAVEMENT MARKING LINE 8"	THERMOPLASTIC PAVEMENT MARKING LINE 12"
	SQ FT	FOOT		FOOT	FOOT	FOOT
		YELLOW	WHITE	WHITE	WHITE	WHITE
NORTHBOUND	169	1875	2035	1976	362	16
TOTAL	169	3910		1976	362	16

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES - SN 050-0078 NB
 IL ROUTE 251 OVER INTERSTATE ROUTE 80
 F.A.I. ROUTE 80 SECTION (50-2HB)I-1
 LASALLE COUNTY
 STATION 569+41.10

DATE: 01/17/2006
 c:/projects/cm305/details.dgn