

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	150-2HB)I-1	LASALLE	26	5
ILLINOIS			STATE PROJECT	

LOCATION	BITUMINOUS CONCRETE REMOVAL (DECK)	WATERPROOFING MEMBRANE SYSTEM	BITUMINOUS CONCRETE SURFACE CSE. SUPERPAVE MIX "D", N70
	SQ YD	SQ YD	TON
STAGE I - DECK	374	340	29
STAGE II - DECK	306	340	29
TOTAL	680	680	58

LOCATION	CONCRETE REMOVAL	CONCRETE SUPERSTRUCTURE
	CU YD	CU YD
STAGE I - PARAPET	0.95	0.95
STAGE II - PARAPET	0.95	0.95
TOTAL	1.90	1.90

LOCATION	BRIDGE HANDRAIL REMOVAL
	STAGE I - PARAPET
STAGE II - PARAPET	204
TOTAL	408

LOCATION	SILICONE JOINT SEALER 1.5" FOOT
	STAGE I - DECK
STAGE II - DECK	38
TOTAL	75

LOCATION	PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	WORKZONE PAVEMENT MARKING REMOVAL
	SQ FT	FOOT	SQ FT
STAGE I	413	1477	487
STAGE II	253	1472	486
TOTAL	666	2949	973

LOCATION	THERMOPLASTIC PAVEMENT MARKING L & S	THERMOPLASTIC PAVEMENT MARKING LINE 4"		THERMOPLASTIC PAVEMENT MARKING LINE 6"	THERMOPLASTIC PAVEMENT MARKING LINE 8"	THERMOPLASTIC PAVEMENT MARKING LINE 12"
	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT
		YELLOW	WHITE	WHITE	WHITE	WHITE
SOUTHBOUND		708	1047	950	57	
TOTAL		1755		950	57	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES - SN 050-0077 SB
 IL ROUTE 251 OVER INTERSTATE ROUTE 80
 F.A.I. ROUTE 80 SECTION (50-2HB)I-1
 LASALLE COUNTY
 STATION 569+41.10

DATE: 01/17/2006
 c:/projects/cmain07/cm305/details.dgn