

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	(128BR)-1	TAZEWELL	30	5
STA. 77+63.98		TO STA. 78+48.02		
FED. ROAD DIST. NO. 4   ILLINOIS   FED. AID PROJECT				

# SUMMARY OF QUANTITIES

## CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE		TOTAL
			X080-2A	SFTY-3N	
			100% STATE		
50300300	PROTECTIVE COAT	SQ. YD.	294		294
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ. FT.	299		299
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ. FT.	2646		2646
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4960		4960
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	244		244
51500100	NAME PLATES	EACH	1		1
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4		4
* 63300205	REMOVAL & RE-INSTALLMENT OF EXISTING STEEL PLATE BEAM				
*	GUARD RAIL, TYPE A	FOOT	50		50
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	4		4
67100100	MOBILIZATION	LSUM	1		1
70100405	TRAFFIC CONTROL AND PROTECTION STANDARD 701321	EACH	1		1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70106700	TEMPORARY RUMBLE STRIP	EACH	12		12
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	176		176
70300200	TEMPORARY PAVEMENT MARKING	FOOT	7040		7040
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	2405		2405
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500		500

\* SPECIALTY ITEM

DATE  
NAME  
SCALE  
REFERENCE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE 03-24-2006

DRAWN BY CEJ  
CHECKED BY