

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
701	(128BR)-1	TAZEWELL	30	6
STA. 77+63.98		TO STA. 78+48.02		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

# SUMMARY OF QUANTITIES

## CONSTRUCTION TYPE CODE

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE		
			X080-2A	SFTY-3N	TOTAL
			100% STATE		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	500		500
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3520		3520
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4		4
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SQ. FT.	1173		1173
X0301852	DEWATERING STRUCTURE NO.1	EACH	1		1
X0323655	GABION ANCHOR STAKE	EACH	103		103
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ. FT.	299		299
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX "D", N50	TON	37		37
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	8		8
X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	294		294
X0325294	PREFORMED JOINT STRIP SEAL	FOOT	40		40
Z0002600	BAR SPLICERS	EACH	94		94
Z0030255	IMPACT ATTENUATORS, TEMPORARY(FULLY REDIRECTIVE, NARROW),				
	TEST LEVEL 2	EACH		2	2
Z0030320	IMPACT ATTENUATORS, RELOCATE(FULLY REDIRECTIVE), TEST LEVEL 2	EACH		2	2

\* SPECIALTY ITEM

PLOT DATE \* DATE \*  
 PLOT SCALE \* SCALE \*  
 REFERENCE \* REF \*

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.      DRAWN BY CEJ  
 HORIZ.              CHECKED BY  
 DATE 03-24-2006