

# SUMMARY OF QUANTITIES

|                       |              |          |                  |           |
|-----------------------|--------------|----------|------------------|-----------|
| F. A. P. NO.          | SECTION      | COUNTY   | SITE SHEETS      | SHEET NO. |
| 646                   | 1103-1N-5,TS | PEORIA   |                  | 5         |
| STA.                  |              | TO STA.  |                  |           |
| FED. ROAD DIST. NO. & |              | ILLINOIS | FED. AID PROJECT |           |

| SUMMARY OF QUANTITIES |   |      | URBAN<br>TOTAL<br>QUANTITIES | CONSTRUCTION TYPE CODE            |                                      |                        |                                  |
|-----------------------|---|------|------------------------------|-----------------------------------|--------------------------------------|------------------------|----------------------------------|
| CODE NO.              | ITEM  | UNIT |                              | FED - STATE<br>90 - 10<br>J000-1A | FED-STE-CTY<br>90-6.7-3.3<br>Y031-1F | CITY<br>100<br>Y030-1E | FED-STE-CTY<br>90-5-5<br>SFTY-1B |
| 81012800              | CONDUIT IN TRENCH, 3" DIA., PVC                                     | FOOT | 37                           |                                   | 37                                   |                        |                                  |
| 81012900              | CONDUIT IN TRENCH, 3 1/2" DIA., PVC                                 | FOOT | 20                           |                                   | 20                                   |                        |                                  |
| 81021350              | CONDUIT PUSHED, 3" DIA., PVC  | FOOT | 135                          |                                   | 135                                  |                        |                                  |
| 81021360              | CONDUIT PUSHED, 3 1/2" DIA., PVC                                    | FOOT | 110                          |                                   | 110                                  |                        |                                  |
| 81400400              | CONCRETE HANDHOLE   | EACH | 1                            |                                   | 1                                    |                        |                                  |
| 81500200              | TRENCH AND BACKFILL FOR ELECTRICAL WORK                             | FOOT | 223                          |                                   | 223                                  |                        |                                  |
| 81702130              | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6            | FOOT | 796                          |                                   |                                      | 796                    |                                  |
| 82102400              | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT                 | EACH | 2                            |                                   |                                      | 2                      |                                  |
| 83054140              | LIGHT POLE, STEEL GALVANIZED, TRANSFORMER BASE, 45 FT. M.H., 12 FT. | EACH | 1                            |                                   | 1                                    |                        |                                  |
| 83600100              | LIGHT POLE FOUNDATION   | EACH | 1                            |                                   | 1                                    |                        |                                  |
| 85700205              | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL               | EACH | 1                            |                                   | 1                                    |                        |                                  |
| 87301225              | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C                         | FOOT | 474                          |                                   | 474                                  |                        |                                  |
| 87301245              | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C                         | FOOT | 1647                         |                                   | 1647                                 |                        |                                  |
| 87301255              | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C                         | FOOT | 290                          |                                   | 290                                  |                        |                                  |
| 87502480              | TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.                        | EACH | 1                            |                                   | 1                                    |                        |                                  |

\* SPECIALTY ITEMS