CONTRACT NO. 68600

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	(103-1)N-5,TS	PEORIA		9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

28000510 - INLET FILTERS	
LOCATION	EACH
KNOXVILLE AVE. - IL 40	
LT. STA. 138+07	1
TOTAL	1

54215967 - REINFORCED CONCRETE PIPE ELBOW 12"	
LOCATION	EACH
PROSPECT RD.	
LT. STA. 0+60	1
TOTAL	1

54248515 - CONCRETE COLLAR	
LOCATION	EACH
KNOXVILLE - IL 40	
LT. STA. 138+07	1
PROSPECT RD.	
RT. STA. 0+80	1
TOTAL	2

550A0050 - STORM SEWERS, CLASS A, TYPE 1 12"	
LOCATION	FOOT
KNOXVILLE- IL 40	
LT. STA. 138+05 TO 138+07	6.3
PROSPECT RD.	
LT. STA. 0+60	10
TOTAL	16

60201305 - CATCH BASINS, TYPE A, 4'-DIA, TYPE 15 FRAME AND LID	
LOCATION	EACH
PROSPECT RD.	
STA. 0+80	1
TOTAL	1

60218400 - MANHOLES, TYPE A, 4'-DIA, TYPE 1 FRAME, CLOSE LID	
LOCATION	EACH
PROSPECT RD.	
STA. 0+60	1
TOTAL	1

60241800 - INLETS, TYPE G-1	
LOCATION	EACH
KNOXVILLE- IL 40	
LT. STA. 138+07	1
TOTAL	1

#4001702 - REMOVE AND REINSTALL INLETS, TYPE G-1, SPECIAL	
LOCATION	EACH
PROSPECT RD.	
STA. 2+31.5	1
TOTAL	1

X0323426 - SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	
LOCATION	EACH
KNOXVILLE AVE. - IL 40	
LT. STA. 138+07	1
TOTAL	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/31/2006
FILE NAME = c:\projects\safety\il40_prospect\misc.dgn
PLOT SCALE = 48.0000 ' / IN.
USER NAME = ghudsmean