CONTRACT NO. 68600

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	(103-1)N-5,TS	PEORIA		10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

78001100 - PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	
LOCATION	SQ. FT.
PROSPECT	
2 RT. TURN ARROWS	17.6
2 LT. TURN ARROWS	17.6
2 "ONLY"	23.6
(SMALL SIZE USED)	
TOTAL	59

78001110 - PAINT PAVEMENT MARKING - LINE 4"	
LOCATION	FOOT
PROSPECT	
WHITE SKIP DASH	44.84
WHITE SOLID E.O.P.	357.63
YELLOW SOLID (MEDIAN)	321.98
DOUBLE YELLOW (MEDIAN)	668.00
TOTAL	1392

78001130 - PAINT PAVEMENT MARKING - LINE 6"	
LOCATION	FOOT
PROSPECT	
2 - CROSSWALK	72.3
TOTAL	72

78001140 - PAINT PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
PROSPECT	
LANE DIVIDER	86.89
TOTAL	87

78001150 - PAINT PAVEMENT MARKING - LINE 12"	
LOCATION	FOOT
PROSPECT	
CROSSWALK BARS	102.00
MEDIAN CHEVERONS	50.00
TOTAL	152

78001180 - PAINT PAVEMENT MARKING - LINE 24"	
LOCATION	FOOT
PROSPECT	
2 - STOP BARS	31.9
TOTAL	32

78100100 - RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
PROSPECT	2
TOTAL	2

78200300 - PRISMATIC CURB REFLECTOR	
LOCATION	EACH
PROSPECT	12
TOTAL	12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/31/2006
FILE NAME = c:\projects\safety\148_prospect\miso.dgn
PLOT SCALE = 48.0000 ' / IN.
USER NAME = ghudsneen