



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2006

SUBJECT: FAP Route 332
Section 48B
Vermilion County
Contract No. 70462
Item No. 141, June 16, 2006 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised pages 6 and 7 of the Special Provisions.
3. Revised sheets 2, 5, 6, 17, 23-27 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by 'P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 5; Roger Driskell; Estimates; Design & Environment File

RS/cab

PRECAST CONCRETE BOX CULVERTS

5-540PD3-98
Eff 07-07-1998

Rev 02-11-2004

Revise the fourth paragraph of Article 540.06 of the Standard Specifications to read:

The excavation and backfilling for precast concrete box culvert shall be according to the requirements of Section 502 except a layer of porous granular material, at least 6 inches (150 mm) in thickness, shall be placed below the elevation of the bottom of the box. The porous granular material shall be gradation CA 7 and shall be placed to extend at least 2 ft. (600 mm) beyond each side of the box. The precast concrete box culvert shall be laid according to the applicable requirements of Article 542.04(d).

SEEDING

5-250PD17-94
Eff. 09-11-90

Rev.: 01-01-97

Earth slopes which are disturbed as a result of the channel excavation as shown on the Channel cross section, soil disturbed from structure removal as shown on proposed typical cross sections shall be seeded with Class 4B Seeding, fertilized and mulched in accordance with Method 2 in accordance with the applicable portions of Sections 250 and 251 of the Standard Specifications. Measurement for payment shall not be greater than as shown in the typical cross sections. Areas outside the limits shown on the typical cross sections which are disturbed by the Contractor's operations shall also be seeded, fertilized and mulched in accordance with the General Notes included in the plans and with Sections 250 and 251 of the Standard Specifications, and will not be measured for payment.

The Contractor shall specify at the time of the preconstruction conference which procedure method of mulching he/she plans to use.

This work will be paid for at the contract unit price for the items used, measured as specified herein and in the Standard Specifications and no additional compensation will be allowed.

TREE REMOVAL AND TREE PROTECTION AND PRESERVATION

This project is located along a small channel that empties into the North Fork Vermilion River. The channel flows through the back yards of two single family residences. It is the intent of this project to protect and leave as many trees as possible in an effort to preserve the wooded setting of the adjacent properties. It is the responsibility of the Contractor to visit the work site to assess the number trees and conditions in the area. This work shall be done in accordance with Section 201 of the Specifications.

In an effort to reduce the number of trees to be removed the Contractor will protect any trees that are to remain in place and may be impacted by the construction work in the channel area. The Contractor will protect trees designated by the Engineer in accordance with Section 201.05 of the Specifications. This work will be measured for payment on a lump sum basis.

Revised 6/5/06

The Contractor will consult with the Engineer before removal of any trees in the project area. Tree removal will be done in accordance with section 201.04 of the specifications and measured for payment on a unit basis.

The protection of trees in the project area will be paid at the unit lump sum price for TREE PROTECTION AND PRESERVATION. The removal of trees in the project area will be paid for at the unit price per unit for TREE REMOVAL (6 TO 15 UNITS DIAMETER), and TREE REMOVAL (OVER 15 UNITS DIAMETER).

STATUS OF UTILITIES

The following utilities are involved in this project. The utility companies have provided the estimated dates.

<u>Name & Address of Utility</u>	<u>Type & Location</u>	<u>Estimated Date Relocation Completed</u>
Mr. Randy Lusk * Village of Rossville 120 E Attica Rossville, IL 60963 (217) 748-6914	Water – Throughout jobsite Sanitary – Throughout jobsite	Not required Not required
Mr. Greg Curtis * Verizon North, Inc. ILL0301 212 E Grove St Rantoul, IL 61866 (217) 892-3359	Telephone – Throughout jobsite	Not required
Mr. Frank Lemezis * Charter Communications 1209 N. State St. PO Box 129 Westville, IL 61883 (217) 267-3196 Mob: (217) 304-1930	Cable TV – Throughout jobsite Coax and fiber optic 4' east of east curb	Not required
Mr. Bruce Kallal * AMEREN-CIPS Rte 9 East 1205 East Pells Street PO Box 23 Paxton, IL 60957 (217) 379-5441 Mob: (217) 649-0291	Electric – Throughout jobsite Gas – Throughout jobsite	Not required Not required

Revised 6/5/06