

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	48B	VERMILION	27	6

70462

SUMMARY OF QUANTITIES

CONTRACT NO. 70462

LOCATION OF WORK:

VERMILION COUNTY
RURAL
ROADWAY / STRUCTURE
IMPROVEMENTS
FAP 332
STA. 824+60
STA. 824+94
100% STATE
X028-2A

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	
* A2015990	TREE, FAGUS SYLVATICA, EUROPEAN BEECH, 1-1/2" BALLED AND BURLAPPED	EACH	2.0	2.0
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	434	434
20100310	TREE REMOVAL, SPECIAL (6 TO 15 UNITS DIAMETER)	UNIT	100.0	100.0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	149	149
20300100	CHANNEL EXCAVATION	CU YD	1,219.0	1,219.0
20900110	POROUS GRANULAR BACKFILL	CU YD	238.0	238.0
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100.0	100.0
* 25000314	SEEDING, CLASS 4B	ACRE	0.5	0.5
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45.0	45.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45.0	45.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45.0	45.0
* 25100115	MULCH, METHOD 2	ACRE	0.5	0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50.0	50.0
28000300	TEMPORARY DITCH CHECKS	EACH	4.0	4.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0	1.0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	170.0	170.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	68.0	68.0
44000600	SIDEWALK REMOVAL	SQ FT	170.0	170.0
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	159.0	159.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0	1.0
51500100	NAME PLATES	EACH	1.0	1.0
54001000	BOX CULVERT END SECTIONS	EACH	2.0	2.0
54021204	PRECAST CONCRETE BOX CULVERT 12' X 4' (M273)	FOOT	66.0	66.0

* SPECIALITY ITEM

△ REVISED 6/5/06