

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	48B	VERMILION	27	12

CONTRACT NO. 70462

TREE PLANTING

CHANNEL	STATION TO	STATION	TREE, FAGUS SYLVATICA, EUROPEAN BEECH, 1-1/2" BALLED AND BURLAPPED (EACH)	TREE, ACER SACCHARUM (SUGAR MAPLE), 3" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, QUERCUS PALUSTRIS (PIN OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED (EACH)	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 3" CALIPER, BALLED AND BURLAPPED (EACH)
	10+00	17+00	2	2	1	1	2

SEEDING

CHANNEL	STATION TO	STATION	SEEDING, CLASS 4B (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 2 (ACRE)	TEMPORARY EROSION CONTROL SEEDING (POUND)
	10+00	17+00	0.5	45.0	45.0	45.0	0.5	50.0
TOTAL			0.5	45.0	45.0	45.0	0.5	50.0

SHORT - TERM PAVEMENT MARKING

ILL 1	STATION TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
	824+60	824+94	34	8	4	0
SUB -TOTALS				8	4	0
TOTAL = 12 FOOT						

PAINT PAVEMENT MARKING - LINE 4"

ILL 1	STATION TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
	824+60	824+94	34	68	9	0
SUB -TOTALS				68	9	0
TOTAL = 77 FOOT						

TEMPORARY PAVEMENT MARKING - LINE 4"

ILL 1	STATION TO	STATION	LENGTH	4" WHITE (FOOT)	4" SKIP DASH YELLOW (FOOT)	4" NO PASSING YELLOW (FOOT)
	824+60	824+94	34	68	9	0
SUB -TOTALS				68	9	0
TOTAL = 77 FOOT						