CONTRACT NO. 72A39

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FR55	(84-2-1)RS3	SANGAMON	5	4
STA.		TO STA.		
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

Agggregate Prime Coat 0.002 Ton/SY
Bituminous Materials (prime coat) 0.00038 Ton/SY
Bituminous Materials (Cover Coat) 0.4 gal/SY
Pavement Width 20 ft
Cover Coat Aggregate 25 lb/SY
Bituminous binder thickness 0.75 in
Bituminous Materials (Seal Coat) 0.4 gal/SY
Bituminous binder density 0.056 Ton/SY*in
Seal Coat Aggregate 25 lb/SY

Station to Station	Length (FT)	Area (SQ YD)	BIT LEVEL BINDER (TON)	AGG PRIME COAT (TON)	BIT PRIME COAT (TON)	BIT MATS A-2 COVER (GAL)	BIT MATS A-2 SEAL (GAL)	AGG A-2 COVER (GAL)	AGG A-2 SEAL (GAL)
232+00 to 51+42	18058	40129	1685	15	80	16052	16052	501.6	501.6
51+42 to 36+88.88	1453	3230	--	--	--	1292	1292	40.4	40.4
290+44.95 to 296+00	555	1233	--	--	--	493	493	15.4	15.4
96+00 to 137+75	4175	9278	--	--	--	3711	3711	116.0	116.0
TOTALS:	24241	53870	1685	15	80	21548	21548	673	673

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FR I-55
(FR I-55 WEST)
SECTION (84-2-1)RS-3;(84-1-2)RS-3
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DRAWN BY
DATE
CHECKED BY