

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70		FAYETTE	20	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* (26-0 & 26-1)RS-3, (26-2)RS-2				

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN I000	RURAL I000
X0325431	CLASS A PATCHES, TYPE II, 17 1/2 INCH	SQ YD	446	419	27
X0325432	CLASS A PATCHES, TYPE III, 17 1/2 INCH	SQ YD	16	16	
X0325433	CLASS A PATCHES, TYPE IV, 17 1/2 INCH	SQ YD	547	547	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	30,316	8823	21,493
40600300	AGGREGATE (PRIME COAT)	TON	406	176	430
40600990	TEMPORARY RAMP	SQ YD	128	128	
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	467	48	419
44200624	CLASS A PATCHES, TYPE 3, 14 INCH	SQ YD	16		16
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	27		27
44213000	PATCHING REINFORCEMENT	SQ YD	1519	1030	489
44213200	SAW CUTS	FOOT	7971	4515	3456
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	1	4
67100100	MOBILIZATION	L SUM	1	0.3	0.7
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	8	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.3	0.7
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.3	0.7
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	8	2	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19645	5717	13928
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	211787	57402	154385
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	27284	7940	19344
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	670	670	
70300275	TEMPORARY PAVEMENT MARKING - LINE 18"	FOOT	48		48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6549	1906	4643
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	27284	7940	19344
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	211787	57402	154385
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	670	670	
* 78005170	EPOXY PAVEMENT MARKING - LINE 18"	FOOT	48		48
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2726	793	1933
X0322729	MATERIAL TRANSFER DEVICE	TON	33,954	9,881	24,873
X4063500	PRELIMINARY TEST STRIP	EACH	1		1
X4066530	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE D, N105	TON	33,954	9,881	24,873
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	303,164	88,225	214,939
X4421000	PARTIAL DEPTH PATCHING	TON	294	275	19

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN I000	RURAL I000
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SQ YD	690	634	56
Z0075300	TIE BARS	EACH	212	203	9
Z0076600	TRAINEES	HOOR	500	150	350

© Y000  
\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
DATE: HORIZ.

DRAWN BY  
CHECKED BY

district  
10/24/2005  
c:\projects\74061\d04104pa.dgn  
PS 6

PLOT DATE = 10/24/2005  
FILE NAME = 4104104pa.dgn  
PLOT SCALE = 1/8"=1'-0"  
USER NAME = district

Rev.