CONTRACT NO. 74061

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	FAYETTE	20	5

STA. TO STA.

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

* (26-0 & 26-1)RS-3, (26-2)RS-2

PAVING SCHEDULE

STATION TO STATION	LENGTH	BITUMINOUS SURFACE REMOVAL 2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	MATERIAL TRANSFER DEVICE	EPOXY PAVEMENT MARKING - LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B LINE - 6"	EPOXY PAVEMENT MARKING - LINE 8"	EPOXY PAVEMENT MARKING - LINE 18"	RAISED REFLECTIVE PAVEMENT MARKER	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 18"
	FOOT	SQ YD	GALLON	TON	TON	TON	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT
EAST BOUND																	
3033+80.00 TO 3035+90.00	210.0	583.3	58.3	1.2	65.3	65.3	420.0	52.5			5.0	37.8	12.6	420.0	52.5		
3035+90.00 TO 3038+74.48	284.5	790.2	79.0	1.6	88.5	88.5	569.0	71.1			7.0	51.2	17.1	569.0	71.1		
3038+74.48 BK=1505+44.20AH																	
1505+44.20 TO 1533+23.70	2779.5	7720.8	772.1	15.4	864.7	864.7	5559.0	694.9			69.0	500.3	166.8	5559.0	694.9		
1533+23.70 TO 1533+76.30	52.6	146.1	14.6	0.3	16.4	16.4	105.2	13.1			1.0	9.5	3.2	105.2	13.1		
1533+76.30 TO 1547+84.15	1407.9	3910.7	391.1	7.8	438.0	438.0	2815.7	352.0			35.0	253.4	84.5	2815.7	352.0		
1547+84.15 TO 1551+15.45	331.3																
1551+15.45 TO 1573+87.00	2271.5	6309.9	631.0	12.6	706.7	706.7	4543.1	567.9			57.0	408.9	136.3	4543.1	567.9		
1573+87.00 TO 1574+13.00	26.0	72.2	7.2	0.1	8.1	8.1	52.0	6.5			1.0	4.7	1.6	52.0	6.5		
1574+13.00 TO 1594+05.45	1992.5	5534.6	553.5	11.1	619.9	619.9	3984.9	498.1			50.0	358.6	119.5	3984.9	498.1		
1594+05.45 TO 1595+10.70	105.3																
1595+10.70 TO 1610+33.67	1523.0	4230.5	423.0	8.5	473.8	473.8	3045.9	380.7			38.0	274.1	91.4	3045.9	380.7		
1610+33.67 BK= 90+55.19AH																	
90+55.19 TO 119+43.67	2888.5	8023.6	802.4	16.0	898.6	898.6	5777.0	722.1			72.0	519.9	173.3	5777.0	722.1		
119+43.67 TO 120+56.49	112.8																
120+56.49 TO 124+96.46	440.0	1222.1	122.2	2.4	136.9	136.9	879.9	110.0			11.0	79.2	26.4	879.9	110.0		
124+96.46 TO 126+74.64	178.2																
126+74.64 TO 137+21.96	1047.3	2909.2	290.9	5.8	325.8	325.8	2094.6	261.8			26.0	188.5	62.8	2094.6	261.8		
137+21.96 TO 139+55.16	233.2																
139+55.16 TO 237+00.00	9744.8	27069.0	2706.9	54.1	3031.7	3031.7	19489.7	2436.2			244.0	1754.1	584.7	19489.7	2436.2		
237+00.00 TO 377+21.00	14021.0	38947.2	3894.7	77.9	4362.1	4362.1	28042.0	3505.3		24.0	351.0	2523.8	841.3	28042.0	3505.3		24.0
377+21.00 TO 380+43.00	322.0	894.4	89.4	1.8	100.2	100.2	523.0	80.5			8.0	58.0	19.3	523.0	80.5		
380+43.00 TO 380+71.00	28.0	77.8	7.8	0.2	8.7	8.7	28.0	7.0			1.0	5.0	1.7	28.0	7.0		
380+71.00 TO 397+80.00	1709.0	4747.2	474.7	9.5	531.7	531.7	2899.0	427.3	135.0		43.0	307.6	102.5	2899.0	427.3	135.0	
397+80.00 TO 399+14.06	134.1	372.4	37.2	0.7	41.7	41.7	268.1	33.5			3.0	24.1	8.0	268.1	33.5		
399+14.06 BK= 398+86.83AH																	
398+86.86 TO 455+67.29	5680.4	15779.0	1577.9	31.6	1767.2	1767.2	10320.9	1420.1			142.0	1022.5	340.8	10320.9	1420.1		
455+67.29 TO 456+93.02	125.7																
456+93.02 TO 482+22.90	2529.9	7027.4	702.7	14.1	787.1	787.1	5059.8	632.5			63.0	455.4	151.8	5059.8	632.5		
482+22.90 TO 483+71.40	148.5																
483+71.40 TO 519+40.32	3568.9	9913.7	991.4	19.8	1110.3	1110.3	6364.8	892.2	250.0		89.0	642.4	214.1	6364.8	892.2	250.0	
519+40.32 BK=519A+12.05AH																	
519A+12.05 TO 538A+44.74	1932.7	5368.6	536.9	10.7	601.3	601.3	2913.4	483.2			48.0	347.9	116.0	2913.4	483.2		
WEST BOUND																	
3033+80.00 TO 3035+90.00	210.0	583.3	58.3	1.2	65.3	65.3	420.0	52.5			5.0	37.8	12.6	420.0	52.5		
3035+90.00 TO 3038+74.48	284.5	790.2	79.0	1.6	88.5	88.5	569.0	71.1			7.0	51.2	17.1	569.0	71.1		
3038+74.48 BK=1505+44.20AH																	
1505+44.20 TO 1533+23.70	2779.5	7720.8	772.1	15.4	864.7	864.7	5559.0	694.9			69.0	500.3	166.8	5559.0	694.9		
1533+23.70 TO 1533+76.30	52.6	146.1	14.6	0.3	16.4	16.4	105.2	13.1			1.0	9.5	3.2	105.2	13.1		
1533+76.30 TO 1547+46.74	1370.4	3806.8	380.7	7.6	426.4	426.4	2740.9	342.6			34.0	246.7	82.2	2740.9	342.6		
1547+46.74 TO 1550+78.04	331.3																
1550+78.04 TO 1573+87.00	2309.0	6413.8	641.4	12.8	718.3	718.3	4617.9	577.2			58.0	415.6	138.5	4617.9	577.2		
1573+87.00 TO 1574+13.00	26.0	72.2	7.2	0.1	8.1	8.1	52.0	6.5			1.0	4.7	1.6	52.0	6.5		
1574+13.00 TO 1594+30.94	2017.9	5605.4	560.5	11.2	627.8	627.8	4035.9	504.5			50.0	363.2	121.1	4035.9	504.5		
1594+30.94 TO 1595+36.19	105.3																
1595+36.19 TO 1610+33.67	1497.5	4159.7	416.0	8.3	465.9	465.9	2995.0	374.4			37.0	269.5	89.8	2995.0	374.4		
1610+33.67 BK= 90+55.19AH																	
90+55.19 TO 119+87.51	2932.3	8145.3	814.5	16.3	912.3	912.3	5864.6	733.1			73.0	527.8	175.9	5864.6	733.1		
119+87.51 TO 121+00.33	112.8																
121+00.33 TO 125+75.19	474.9	1319.1	131.9	2.6	147.7	147.7	949.7	118.7			12.0	85.5	28.5	949.7	118.7		
125+75.19 TO 127+53.52	178.3																
127+53.52 TO 138+00.84	1047.3	2909.2	290.9	5.8	325.8	325.8	2094.6	261.8			26.0	188.5	62.8	2094.6	261.8		
138+00.84 TO 140+34.04	233.2																
140+34.04 TO 237+00.00	9666.0	26849.9	2685.0	53.7	3007.2	3007.2	19331.9	2416.5			242.0	1739.9	580.0	19331.9	2416.5		
237+00.00 TO 377+21.00	14021.0	38947.2	3894.7	77.9	4362.1	4362.1	27671.0	3505.3		24.0	351.0	2523.8	841.3	27671.0	3505.3		24.0
377+21.00 TO 380+43.00	322.0	894.4	89.4	1.8	100.2	100.2	322.0	80.5			8.0	58.0	19.3	322.0	80.5		
380+43.00 TO 380+71.00	28.0	77.8	7.8	0.2	8.7	8.7	28.0	7.0			1.0	5.0	1.7	28.0	7.0		
380+71.00 TO 397+80.00	1709.0	4747.2	474.7	9.5	531.7	531.7	3374.0	427.3			43.0	307.6	102.5	3374.0	427.3		
397+80.00 TO 399+14.06	134.1	372.4	37.2	0.7	41.7	41.7	268.1	33.5			3.0	24.1	8.0	268.1	33.5		
399+14.06 BK= 398+86.83AH																	
398+86.86 TO 455+74.71	5687.9	15799.6	1580.0	31.6	1769.6	1769.6	10702.7	1422.0	140.0		142.0	1023.8	341.3	10702.7	1422.0	140.0	
455+74.71 TO 456+98.02	123.3																
456+98.02 TO 482+19.76	2521.7	7004.8	700.5	14.0	784.5	784.5	5043.5	630.4			63.0	453.9	151.3	5043.5	630.4		
482+19.76 TO 483+68.26	148.5																
483+68.26 TO 538+21.70	5453.4	15148.4	1514.8	30.3	1696.6	1696.6	9286.9	1363.4	145.0		136.0	981.6	327.2	9286.9	1363.4	145.0	
TOTALS		303164.0	30316.0	606.0	33954.0	33954.0	211787.0	27284.0	670.0	48.0	2726.0	19645.0	6548.0	211787.0	27285.0	670.0	48.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

RESURFACING & PAVEMENT MARKING SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

REVISED 3/7/2006

PLOT DATE = 3/7/2006
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = district