

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 70	*	ST. CLAIR	111	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT- 1M-70	

* 82-3HVB-3R-3
CONTRACT NO. 76305

SUMMARY OF QUANTITIES			90% FEDERAL 10% STATE URBAN				
CODE NO.	CONSTRUCTION CODE TYPE ITEM	UNIT	QUANTITIES				
			TOTAL	ROADWAY J000	SN 082-0144 ROADWAY D X131-5B	SN 082-0142 RAMP S X531-5B	SN 082-0254 Roadway G X231-2A
4400007	Bituminous Surface Removal-2"	Sq. Yd.	140	140	---	---	---
44000800	Bituminous Concrete Curb Removal	Foot	15	---	15	---	---
44000910	Bituminous Concrete Removal (Deck)	Sq. Yd.	10,972	---	5,019	5,737	216
50102400	Concrete Removal	Cu. Yd.	1,847.2	---	629	1,174	44.2
50300160	Neoprene Expansion Joint-4"	Foot	96	---	45	28	23
50300225	Concrete Structures	Cu. Yd.	10.0	---	10.0	---	---
50300255	Concrete Superstructure	Cu. Yd.	1,677.6	---	570	1,067	40.6
50300260	Bridge Deck Grooving	Sq. Yd.	11,750	---	5,090	6,456	204
50300300	Protective Coat	Sq. Yd.	17,718	---	7,214	10,250	254
50300310	Elastomeric Bearing Assembly, Type I	Each	5	---	5	---	---
50300320	Elastomeric Bearing Assembly, Type II	Each	4	---	---	4	---
50500105	Furnishing and Erecting Structural Steel	L Sum	1	---	0.49	0.51	---
50500715	Jack and Remove Existing Bearings	Each	17	---	13	4	---
50600600	Cleaning and Painting Steel Bridge, No. 1	L Sum	1	---	1	---	---
50600700	Cleaning and Painting Steel Bridge, No. 2	L Sum	1	---	---	1	---
50606401	Containment and Disposal of Lead Paint Cleaning Residues, No. 1	L Sum	1	---	1	---	---
50606402	Containment and Disposal of Lead Paint Cleaning Residues, No. 2	L Sum	1	---	---	1	---
50800205	Reinforcement Bars, Epoxy Coated	Pound	246,910	---	89,880	152,080	4,950
* 63000000	Steel Plate Beam Guard Rail, Type A	Foot	10	10	---	---	---
* 63200710	Steel Plate Beam Guard Rail Removal, Type A	Foot	28	28	---	---	---
* 63300730	Steel Plate Beam Guard Rail, Steel Post	Each	1	1	---	---	---
67000400	Engineer's Field Office, Type A	CAL MO	24	24	---	---	---
67000600	Engineer's Field Laboratory	CAL MO	24	24	---	---	---
67100100	Mobilization	L Sum	1	1	---	---	---
70100205	Traffic Control and Protection, Standard 701401	Each	4	4	---	---	---
70100420	Traffic Control and Protection, Standard 701411	Each	2	2	---	---	---
70101800	Traffic Control and Protection (Special)	L Sum	1	1	---	---	---
70300220	Temporary Pavement Marking-Line, 4"	Foot	13,000	13,000	---	---	---
70300240	Temporary Pavement Marking-Line, 6"	Foot	6,000	6,000	---	---	---
70301000	Work Zone Pavement Marking Removal	Sq. Ft.	7,400	7,400	---	---	---
70400500	Temporary Concrete Barrier (State Owned)	Foot	1,600	1,600	---	---	---
70400600	Relocate Temporary Concrete Barrier (State Owned)	Foot	3,200	3,200	---	---	---
* 78001110	Paint Pavement Marking-Line 4"	Foot	9,450	9,450	---	---	---
* 78001140	Paint Pavement Marking-Line 8"	Foot	1,060	1,060	---	---	---
* 78001150	Paint Pavement Marking-Line 12"	Foot	250	250	---	---	---
* 78100105	Raised Reflective Pavement Marker (Bridge)	Each	29	29	---	---	---
78200100	Unidirectional Prismatic Barrier Reflector	Each	120	120	---	---	---
78300100	Pavement Marking Removal	Sq. Ft.	2,150	2,150	---	---	---
70102020	Traffic Control and Protection Standard 701501	L-Sum	1	1	---	---	---

Note: Summary of quantities continued on next sheet.

* SPECIALTY ITEMS

DATE: 4/29/2006 FILENAME: P:\2001\1201\1300\2001\240\drafting\roadwayrehab_da\ver, index, and staging\ds_sq1.dgn

DESIGNED	JEL
CHECKED	MJS
DRAWN	CLK
CHECKED	JEL

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES
STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
REHABILITATION AND RETROFIT REPAIRS
FAI ROUTE 70
POPLAR STREET BRIDGE APPROACHES
ST. CLAIR COUNTY

STRUCTURE NO.
SCALE: N.T.S.
DATE: 2/28/2006

Rev.