

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 70	*	ST. CLAIR	111	4
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT- 111-78	

82-3HVB-3R-3
CONTRACT NO. 76305

SUMMARY OF QUANTITIES (CONTINUED)			90% FEDERAL 10% STATE URBAN				
CODE NO.	CONSTRUCTION CODE TYPE ITEM	UNIT	TOTAL	QUANTITIES			
				ROADWAY J000	SN 082-0144 ROADWAY D X131-5B	SN 082-0142 RAMP S X531-5B	SN 082-0254 ROADWAY G X231-2A
X0321744	Silicone Joint Sealer-2"	Foot	190	---	190	---	---
X0321781	Mechanical Splice	Each	1,008	---	514	458	36
X0322556	Stiffener Intersection Modification	Each	432	---	432	---	---
X0325397	Long Span Floor Beam Retrofit	Each	10	---	10	---	---
X0322559	Bolt Replacement	Each	116	---	72	44	---
X0322560	Crack Extension Modifications	Each	45	---	20	20	5
Xx004814	Silicone Joint Sealer -3"	Foot	120	---	64	56	---
X0320887	Polymer Concrete	Cu. Ft.	46.3	---	37.0	3.1	6.2
X0323080	Drainage Scuppers, DS12	Each	58	---	31	22	5
X4066418	Bituminous Concrete Surface Course, Superpave, Mix "C" N90	Ton	16	16	---	---	---
X7015000	Changeable Message Sign	CAL M0	24	24	---	---	---
XZ191200	Bridge Deck Microsilica Concrete Overlay-2 1/2"	Sq. Yd.	10,815	---	4,155	6,456	204
Z0002600	Bar Splicers	Each	322	---	322	---	---
XZ191215	Bridge Deck Microsilica Concrete Overlay-4"	Sq. Yd.	1,205	---	1,205	---	---
Z0006215	Bridge Deck Hydro-Scarification-2"	Sq. Yd.	1,125	---	1,125	---	---
Z0006204	Bridge Deck Hydro-Scarification-1/2"	Sq. Yd.	9,847	---	3,894	5,737	216
Z0016002	Deck Slab Repair (Full Depth, Type II)	Sq. Yd.	4	---	4	---	---
Z0022400	Fabric Reinforced Elastomeric Trough	Foot	170	---	54	116	---
Δ Z0030250	Impact Attenuator, Temporary (Non-Redirective), Test Level 3	Each	1	1	---	---	---
Δ Z0030350	Impact Attenuator, Relocate (Non-Redirective), Test Level 3	Each	1	1	---	---	---
Z0047300	Protective Shield	Sq. Yd.	3,350	---	1,780	1,570	---
Z0048665	Railroad Protective Liability Insurance	L Sum	1	1	---	---	---
Z0050000	Removal and Reinstallation of Existing Impact Attenuators	Each	1	1	---	---	---
z0018800	Drainage System	L Sum	1	---	0.33	0.67	---
x0323102	Seismic Isolation Bearing Assembly, Type A	Each	8	---	8	---	---
X0325396	Temporary Repair of Staged Construction Joint	Foot	1,200	1,200	---	---	---
⊙ Z0076600	TRAINEES	Hour	1,500	1,500			

Note: Summary of Quantities continued from Previous Sheet.

Δ - SFTY-3N
⊙ Y080

DATE: 4/18/2006 FILENAME: P:\2001\1201-1300\2001.1240\drafting\roadwayrehab\ds\cover_index_and_aging\ds_sqg2.dgn

DESIGNED	JEL
CHECKED	MJS
DRAWN	CLK
CHECKED	JEL

REVISIONS	
NAME	DATE

SUMMARY OF QUANTITIES II
STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
REHABILITATION AND RETROFIT REPAIRS
FAI ROUTE 70
POPLAR STREET BRIDGE APPROACHES
ST. CLAIR COUNTY
STRUCTURE NO.
SCALE: N.T.S.
DATE: 2/28/2006

Rev.