

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 70	*	ST. CLAIR	111	77
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT- IN-70	

* 82-3HVB-3R-3 SHEET S-10 OF S-44
CONTRACT NO. 76305

Station	Offset	Theo. Elev.	Theo. Elev. Adj. for Δ	Station	Offset	Theo. Elev.	Theo. Elev. Adj. for Δ	Station	Offset	Theo. Elev.	Theo. Elev. Adj. for Δ	Station	Offset	Theo. Elev.	Theo. Elev. Adj. for Δ
772.000	-20.000	465.338	465.339	898.000	-4.000	470.168	470.175	1025.000	-4.000	475.211	475.211	1168.250	-4.000	480.941	480.947
772.000	-12.000	465.484	465.485	898.000	3.917	470.728	470.735	1025.000	3.935	475.846	475.846	1168.250	3.910	481.574	481.580
772.000	-4.000	465.630	465.631	898.000	11.916	471.294	471.301	1025.000	11.935	476.486	476.486	1168.250	11.909	482.214	482.220
772.000	4.000	465.777	465.778	898.000	20.000	471.867	471.874	1025.000	20.000	477.131	477.131	1168.250	20.000	482.861	482.867
781.000	-20.000	465.683	465.686	907.000	-4.000	470.513	470.523	1034.250	-4.000	475.581	475.584	1177.500	-4.000	481.311	481.315
781.000	-12.000	465.859	465.862	907.000	3.859	471.099	471.109	1034.250	3.950	476.217	476.220	1177.500	3.965	481.948	481.952
781.000	-4.000	466.035	466.038	907.000	11.858	471.695	471.705	1034.250	11.949	476.857	476.860	1177.500	11.965	482.588	482.592
781.000	4.000	466.211	466.214	907.000	20.000	472.302	472.312	1034.250	20.000	477.501	477.504	1177.500	20.000	483.231	483.235
790.000	-20.000	466.028	466.035	916.000	-4.000	470.858	470.870	1043.500	-4.000	475.951	475.958	1183.583	-4.000	481.555	481.557
790.000	-12.000	466.234	466.241	916.000	3.917	471.478	471.490	1043.500	3.958	476.588	476.595	1183.583	3.956	482.191	482.193
790.000	-4.000	466.440	466.447	916.000	11.916	472.104	472.116	1043.500	11.958	477.228	477.235	1183.583	11.955	482.831	482.833
790.000	4.000	466.646	466.653	916.000	20.000	472.737	472.749	1043.500	20.000	477.871	477.878	1183.583	20.000	483.475	483.477
799.000	-20.000	466.373	466.383	925.000	-4.000	471.211	471.223	1053.500	-4.000	476.351	476.363	1189.658	-4.000	481.798	481.798
799.000	-12.000	466.609	466.619	925.000	3.960	471.848	471.860	1053.500	1.521	476.793	476.805	1189.673	4.000	482.438	482.438
799.000	-4.000	466.845	466.855	925.000	11.959	472.488	472.500	1053.500	7.062	477.236	477.248	1189.688	12.000	483.079	483.079
799.000	4.000	467.081	467.091	925.000	20.000	473.131	473.143	1053.500	20.000	477.871	477.883	1189.703	20.000	483.719	483.719
808.000	-20.000	466.718	466.730	934.000	-4.000	471.571	471.581	1063.500	-4.000	476.751	476.766				
808.000	-12.000	466.984	466.996	934.000	3.953	472.207	472.217	1063.500	-2.460	476.874	476.890				
808.000	-4.000	467.250	467.262	934.000	11.953	472.847	472.857	1063.500	-0.903	476.999	477.014				
808.000	4.000	467.516	467.528	934.000	20.000	473.491	473.501	1063.500	20.000	478.671	478.686				
817.000	-20.000	467.063	467.076	943.000	-4.000	471.931	471.937	1073.500	-4.000	477.151	477.168				
817.000	-12.000	467.359	467.372	943.000	3.966	472.568	472.574	1073.500	-1.679	477.337	477.354				
817.000	-4.000	467.655	467.668	943.000	11.966	473.208	473.214	1073.500	0.664	477.524	477.541				
817.000	4.000	467.951	467.964	943.000	20.000	473.851	473.857	1073.500	20.000	479.071	479.088				
826.000	-20.000	467.408	467.420	948.833	-4.000	472.164	472.167	1083.500	-4.000	477.551	477.566				
826.000	-12.000	467.734	467.746	948.833	3.959	472.801	472.804	1083.500	2.339	478.058	478.073				
826.000	-4.000	468.060	468.072	948.833	11.958	473.441	473.444	1083.500	8.695	478.567	478.582				
826.000	4.000	468.386	468.398	948.833	20.000	474.084	474.087	1083.500	20.000	479.471	479.486				
835.000	-20.000	467.753	467.763	954.658	-4.000	472.397	472.397	1093.500	-4.000	477.951	477.963				
835.000	-12.000	468.109	468.119	954.673	4.000	473.038	473.038	1093.500	3.940	478.586	478.598				
835.000	-4.000	468.465	468.475	954.688	12.000	473.679	473.679	1093.500	11.939	479.226	479.238				
835.000	4.000	468.821	468.831	954.703	20.000	474.319	474.319	1093.500	20.000	479.871	479.883				
844.000	-20.000	468.098	468.105	957.342	-4.000	472.505	472.505	1103.500	-4.000	478.351	478.358				
844.000	-12.000	468.484	468.491	957.327	4.000	473.144	473.144	1103.500	3.954	478.988	478.995				
844.000	-4.000	468.870	468.877	957.312	12.000	473.784	473.784	1103.500	11.954	479.627	479.634				
844.000	4.000	469.256	469.263	957.297	20.000	474.423	474.423	1103.500	20.000	480.271	480.278				
853.000	-20.000	468.443	468.446	963.417	-4.000	472.748	472.750	1112.750	-4.000	478.721	478.724				
853.000	-12.000	468.857	468.860	963.417	3.910	473.381	473.383	1112.750	3.950	479.357	479.360				
853.000	-4.000	469.273	469.276	963.417	11.909	474.021	474.023	1112.750	11.949	479.997	480.000				
853.000	4.000	469.691	469.694	963.417	20.000	474.668	474.670	1112.750	20.000	480.641	480.644				
862.000	-4.000	468.788	468.789	969.500	-4.000	472.991	472.995	1122.000	-4.000	479.091	479.091				
862.000	3.897	469.228	469.229	969.500	3.873	473.621	473.625	1122.000	3.958	479.728	479.728				
862.000	11.896	469.674	469.675	969.500	11.872	474.261	474.265	1122.000	11.958	480.368	480.368				
862.000	20.000	470.126	470.127	969.500	20.000	474.911	474.915	1122.000	20.000	481.011	481.011				
871.000	-4.000	469.133	469.133	978.750	-4.000	473.361	473.367	1131.250	-4.000	479.461	479.461				
871.000	3.942	469.606	469.606	978.750	3.919	473.995	474.001	1131.250	3.950	480.097	480.097				
871.000	11.942	470.082	470.082	978.750	11.918	474.635	474.641	1131.250	11.949	480.737	480.737				
871.000	20.000	470.561	470.561	978.750	20.000	475.281	475.287	1131.250	20.000	481.381	481.381				
880.000	-4.000	469.478	469.479	988.000	-4.000	473.731	473.737	1140.500	-4.000	479.831	479.833				
880.000	3.953	469.981	469.982	988.000	3.958	474.368	474.374	1140.500	3.958	480.468	480.470				
880.000	11.953	470.487	470.488	988.000	11.958	475.008	475.014	1140.500	11.958	481.108	481.110				
880.000	20.000	470.996	470.997	988.000	20.000	475.651	475.657	1140.500	20.000	481.751	481.753				
889.000	-4.000	469.823	469.827	997.250	-4.000	474.101	474.105	1149.750	-4.000	480.201	480.205				
889.000	3.960	470.356	470.360	997.250	3.950	474.737	474.741	1149.750	3.910	480.834	480.838				
889.000	11.959	470.893	470.896	997.250	11.949	475.377	475.381	1149.750	11.909	481.474	481.478				
889.000	20.000	471.431	471.435	997.250	20.000	476.021	476.025	1149.750	20.000	482.121	482.125				
				1006.500	-4.000	474.471	474.473	1159.000	-4.000	480.571	480.577				
				1006.500	3.935	475.106	475.108	1159.000	3.849	481.199	481.205				
				1006.500	11.935	475.746	475.748	1159.000	11.847	481.839	481.845				
				1006.500	20.000	476.391	476.393	1159.000	20.000	482.491	482.497				
				1015.750	-4.000	474.841	474.841								
				1015.750	3.874	475.471	475.471								
				1015.750	11.872	476.111	476.111								
				1015.750	20.000	476.761	476.761								

- Notes:*
1. All elevations are top of new concrete overlay.
See additional sloping requirements at gutter lines in Detail 1/S35.
2. See Sht. S6 for station numbers and offsets
3. All numbers this sheet are given in feet

TOP OF ROADWAY ELEVATIONS - SPANS S6 - S10

REVISIONS		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION REHABILITATION AND RETROFIT REPAIRS FAI ROUTE 70 POPLAR STREET BRIDGE APPROACHES ST. CLAIR COUNTY STRUCTURE NO. 082-0142 (RAMP 5) SCALE: DATE: 02/28/2006
NAME	DATE	

DATE: 4/19/2006
FILENAME: p:\2001\1201-1300\2001.1240\drafting\roadwayrehab_ds\ramps\elevations\sl0610.dgn

DESIGNED	JPD
CHECKED	JEL
DRAWN	CLK
CHECKED	JEL