

SUMMARY OF QUANTITIES

MAP SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
805	147BR	ST. CLAIR	52	3

EXISTING CONDITIONS:

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X071-2A	X071-2A	SFTY-3N
20200100	EARTH EXCAVATION	CU YD	1045	1045		
20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	414		414	
20400800	FURNISHED EXCAVATION	CU YD	94	94		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	448		448	
25000200	SEEDING, CLASS 2	ACRE	0.3	0.3		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54	54		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54	54		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54	54		
25100115	MULCH, METHOD 2	ACRE	0.3	0.3		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	34	34		
28000400	PERIMETER EROSION BARRIER	FOOT	814	814		
28100109	STONE RIPRAP, CLASS A5	SQ YD	266		266	
28200200	FILTER FABRIC	SQ YD	266		266	
35400520	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 12"	SQ YD	416	416		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.6	3.6		
40600300	AGGREGATE (PRIME COAT)	TON	17	17		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	427	427		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640		
40600990	TEMPORARY RAMP	SQ YD	148	148		
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	544		544	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	109		109	
44000100	PAVEMENT REMOVAL	SQ YD	1413		1413	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3022		3022	
44000700	APPROACH SLAB REMOVAL	SQ YD	287		287	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	3915	3915		
44004250	PAVED SHOULDER REMOVAL	SQ YD	160	160		
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	264	264		
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SQ YD	156	156		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	81	81		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	623		623	
50300225	CONCRETE STRUCTURES	CU YD	87		87	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	410.8		410.8	
50300260	BRIDGE DECK GROOVING	SQ YD	1074		1074	
50300300	PROTECTIVE COAT	SQ YD	1343		1343	

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		X071-2A	X071-2A	SFTY-3N
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	2916		2916	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	95100		95100	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	2064		2064	
51202700	DRIVING STEEL PILES	FOOT	2064		2064	
51203800	TEST PILE STEEL HP14X73	EACH	4		4	
51205200	TEMPORARY SHEET PILING	SQ FT	678		678	
51500100	NAME PLATES	EACH	2		2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	219		219	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	325		325	
60605200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (DOWELLED)	FOOT	1140	1140		
60610600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24 (DOWELLED)	FOOT	1723	1723		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	5838	5838		
60625900	P.C.C. RAMPED MEDIAN TERMINAL	EACH	2	2		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	250	250		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4		
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	222	222		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1	
70101210	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416 (SPECIAL)	EACH	1		1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	180	180		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	864	864		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7294	7294		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6310	6310		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1389		1389	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1219		1219	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	47	47		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6445	6445		

*SPECIALTY ITEMS

DATE: 3/20/2006
 C:\p\jests\ad\1200\plan\pnd84d.dgn
 -REF-