ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
805	147BR	ST. CLAIR	52	3A
STA.		TO STA.		
EXISTING CONDITIONS:				

	SUMMARY OF QUANTITIES			80% FED. 20% STATE	CONSTRUCTION TYPE CODE		
	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X071-2A	X071-2A	SFTY-3N
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1635	1635		
*	78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	36	36		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	49	49		
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	8		8	
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	891	891		
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	49	49		
*	81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	10	10		
*	81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	20	20		
*	81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	115	115		
*	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	30	30		
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	362	362		
*	88600100	DETECTOR LOOP, TYPE I	FOOT	97	97		
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	385	385		
	X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	17	17		
	X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	1089	1089		
	X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	1441	1441		
	X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	645	645		
	X7200200	WIDE LOAD SIGNING	L SUM	1	1		
*	X7800455	POLYUREA PAVEMENT MARKING TYPE 1, RAISED MEDIAN	SQ FT	164	164		
	Z0002600	BAR SPLICERS	EACH	160		160	
	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3			3
	Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3			3
*	Z0049100	RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT	EACH	17	17		
	Z0070100	SURVEY MONUMENT COVER ASSEMBLY	EACH	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT				

* SPECIALTY ITEMS

$$DATE$$
3/20/2006
c:\projects\edl2300\plan\pln040a.dgn
*REF-
*REF-

PLOT DATE: 3/20/2006