

LOCATION		STAGE I	STAGE II	TEMP. CONC. BARRIER	RELOCATE TEMP. CONC. BARRIER	IMPACT ATTENUATOR, RELOC. (NON-REDIR.), TEST LEVEL 2	IMPACT ATTENUATORS, TEMP. (NON-REDIR.) TEST LEVEL 2
				FEET	FEET	EACH	EACH
			X				1
96+44.92	TO	96+07.00	X	1034			
		106+79.08	X				
		97+65.00				1	•
		97+65.00					
97+82.92	TO	107+07.08	X		924		
		97+84.00	X				1
98+21.92	TO	101+77.00	X	355			
101+75.00	TO	104+70.00			295		
		104+70.00				1	•
		107+17.00	X				1
		107+17.00	X				•
		107+45.00				1	•
TOTAL:				1389	1219	3	3

• SHALL BE REUSED FOR STAGE II TRAFFIC CONTROL

LOCATION		SB	NB	SPBGR, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1, SPEC. (TANGENT)	SPBGR REMOVAL	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKER, TYPE A	
				FEET	EACH	EACH	FEET	EACH	MONO DIR. SILVER	MONO DIR. AMBER
ILL. 161 OUTSIDE		X							2	
ILL. 161 INSIDE		X								2
ILL. 161 OUTSIDE			X						2	
ILL. 161 INSIDE			X							2
98+85.97		X						1		
98+85.97	TO	99+23.47	X			1				
99+06.34		X						1		
99+06.34	TO	99+43.84	X			1				
99+06.61	TO	100+17.49	X				111			
99+23.47	TO	99+83.82	X	62.5						
99+43.84	TO	100+04.19	X	62.5						
100+04.19	TO	100+37.34	X		1					
100+04.19	TO	100+37.34	X		1					
101+68.24	TO	102+01.39	X		1					
101+87.63	TO	102+20.78	X		1					
101+89.43	TO	103+00.58	X				111			
102+01.39	TO	102+61.74	X	62.5						
102+20.78	TO	102+81.13	X	62.5						
102+61.74	TO	102+99.24	X			1				
102+81.13	TO	103+18.63	X			1				
102+99.24			X					1		
103+18.63			X					1		
SUBTOTAL				250.0	4	4	222	4	4	4
TOTAL:				250.0	4	4	222	4	4	8

STATION	TO	STATION	SEEDING CLASS 2	TEMP. EROSION CONTROL SEEDING	NUTRIENTS			MULCH METHOD 2
			ACRE	POUND	NITROGEN FERT. NUTR. POUND	PHOSPHORUS FERT. NUTR. POUND	POTASSIUM FERT. NUTR. POUND	ACRE
95+77.38		112+07.43	0.30	34.00	54	54	54	0.3
TOTAL:			0.3	34.0	54.0	54.0	54.0	0.3

STATION	TO	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE FACTOR	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
STA 95+77.38 LT & RT	TO	STA 112+07.43 LT & RT	1045	784	878	0
TOTAL:			1045	784	878	-94

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 FAP ROUTE 805
 SECTION 147BR
 ST. CLAIR COUNTY

DRAWN BY: