

SUMMARY OF QUANTITIES

F.A.U. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9170	124-21	ST. CLAIR	10	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN 100% STATE Y007	
X0325427	CUT CONDUIT IN TRENCH	EACH	2	2	
20200100	EARTH EXCAVATION	CU YD	135	135	
20400800	FURNISHED EXCAVATION	CU YD	426	426	
25000210	SEEDING, CLASS 2A	ACRE	0.23	0.23	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20.7	20.7	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20.7	20.7	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20.7	20.7	
25100115	MULCH, METHOD 2	ACRE	0.23	0.23	
28000300	TEMPORARY DITCH CHECKS	EACH	9	9	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100107	STONE RIPRAP, CLASS A4	SQ YD	55	55	
28200200	FILTER FABRIC	SQ YD	55	55	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	234	234	
44001980	CONCRETE BARRIER REMOVAL	FOOT	125	125	
44004250	PAVED SHOULDER REMOVAL	SQ YD	175	175	
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	105	105	
44201294	CLASS B PATCH-EXPANSION JOINT	FOOT	35	35	
44213100	PAVEMENT FABRIC	SQ YD	105	105	
44213200	SAW CUTS	FOOT	81	81	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	84	84	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	276	276	
54010605	PRECAST CONCRETE BOX CULVERT 6' X 5'	FOOT	54	54	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	149	149	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1	1	
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	400	400	

*SPECIALTY ITEMS

PLOT DATE = 3/13/2005
 FILE NAME = c:\projects\76938\76938.dgn
 PLOT SCALE = 50:0000 / 1" IN.
 REFERENCE = #REF*