F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 83757

	CODE NUMBER	ITEM	UNIT	TOTAL	BITUMINOUS CONCRETE I000-2A	PORTLAND CEMENT CONCRETE J000-2A	STEEL GIRDER BRIDGE OVER WATERWAY X091-2A	PAVEMENT MARKING SFTY-10	HIGHWAY LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F	
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1						
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1						
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	622	622						
*	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9,246	9,246						
*	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,483	1,483						
*	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	42	42						
*	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	414	414						
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,621	3,621						
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	300						
	72000100	SIGN PANEL - TYPE 1	SQ FT	37.5						37.5	
	72000200	SIGN PANEL - TYPE 2	SQ FT	30						30	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	352.4	279.6			72.8			
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,340	1,820			1,520			
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,733	1,093			640			
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	279	248			31			
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	213	148			65			
*	78002100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LETTERS AND SYMBOLS	SQ FT	195.2		195.2					
*	78002110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LINE 4"	FOOT	297		297					
*	78002130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LINE 6"	FOOT	795		795					
*	78002150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LINE 12"	FOOT	59		59					
*	78002180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LINE 24"	FOOT	91		91					
	78200405	GUARDRAIL MARKERS	EACH	16	16						
	78200500	BARRIER WALL MARKERS	EACH	4	4						
	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4						
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,752	2,752						
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	3					3		
*	80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	21					21		
*	80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	1					1		
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	403						403	
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	70						70	
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	295					295		
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	272					80	192	
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	492						492	
*	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	526					526		
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	357						357	
*	81400100	HANDHOLE	EACH	9						9	

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL COUNTY

SUMMARY OF QUANTITIES IV

SCALE: NTS
DATE: 07/01/05
DRAWN BY: PFR
CHECKED BY: KPS

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/565-4500

..\TEDONEZ.DGN,..\SUDDONRB.DGN,..\SUDDONRE.DGN
9-08-2005, 12:13:35
S:\DOCUMENT\023380\CIVIL\DGN\SUQQQQ50.DGN
ROSSPF