

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
089/164/3863	05-00007-00-RS	McHENRY & LAKE	15	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
C-91-128-06		M-8003 (556)		

CONTRACT NO. 83846

CODE NO.	PAY ITEM	UNIT	1000 TOTAL	LINCOLN ROAD	SULLIVAN LAKE ROAD	CUHLMAN ROAD
20800150	TRENCH BACKFILL	CU YD	30	0	30	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,295	792	3,085	1,418
40600300	AGGREGATE (PRIME COAT)	TON	107	16	62	29
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	978	210	673	95
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	344	52	200	92
44000009	BITUMINOUS SURFACE REMOVAL 3"	SQ YD	1,325	198	772	355
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	90	90	0	0
44001435	BITUMINOUS SHOULDER REMOVAL (SPECIAL)	SQ YD	222	0	222	0
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	46	0	46	0
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	926	505	208	213
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	351	45	93	213
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	2,651	45	1,967	639
48101200	AGGREGATE SHOULDERS, TYPE B	TON	773	70	408	295
50105220	PIPE CULVERT REMOVAL	FOOT	82	0	82	0
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	82	0	82	0
54213870	STEEL END SECTIONS 15"	EACH	4	0	4	0
67100100	MOBILIZATION	L SUM	1	0.10	0.62	0.28
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.10	0.62	0.28
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,168	648	3,792	1,728
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,056	216	1,264	576
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	36	36	0	0
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	39,965	3,338	25,222	11,405
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	141	115	0	26
• 78000650	THERMOPLASTIC PAVEMENT MARKINGS - LINE 24"	FOOT	63	17	20	26
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	462	0	318	144
• Z0053700	RESETTING SURVEY MONUMENTS	EACH	1	0	1	0
• X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154	51	51.4	51.4
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	2,740	409	1,597	734
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	231	35	134	62
X4066905	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE IL 4.75, N50	TON	1,144	171	667	306

• INDICATES SPECIALITY ITEM

03/02/2006 09:25:56 AM
 I:\KRM\050271\dgn\050271-sq.dwg
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 84-00101 - EXPIRES 4/30/2007

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	12/21/05	PER IDOT REVIEW
	2	2/27/06	PER IDOT REVIEW

* REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS

DRAWING FILE: ...050271\dgns\050271-sq.dwg

BAXTER
WOODMAN
Consulting Engineers

Baxter & Woodman
Crystal Lake, Illinois 815.489.1260
Burlington, Wisconsin 262.763.7834
Mokena, Illinois 708.478.5090
DeKalb, Illinois 815.787.3111
Grayslake, Illinois 847.223.6088
Rockford, Illinois 815.489.1551

VILLAGE OF LAKEMOOR, ILLINOIS
LINCOLN ROAD, SULLIVAN LAKE ROAD & CUHLMAN ROAD
STP (LAPP) IMPROVEMENTS

SUMMARY OF QUANTITIES

DESIGNED BY	SCALE
MWP	NONE
DRAWN BY	PROJECT NO.
CJC	050271
CHECKED BY	SHEET NO.
MWP	3 OF 15
DATE	
11/15/05	