

# SUMMARY OF QUANTITIES

SHEET 7 OF 8

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	10-32HB-3,K	CHAMPAIGN	352	12

CONTRACT NO. 90758

1000-2A | Y007

LOCATION OF WORK:

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

URBAN

WITHIN ACCESS CONTROL LIMITS				OUTSIDE ACCESS CONTROL LIMITS	
ROADWAY	DITCH DETENTION	STRUCTURE	CSS FEATURES	FOUR-LANE	TWO-LANE
FAI-57 STA. 272+00 TO STA. 323+00		S. N. 010-0272		CURTIS ROAD STA. 1+10.60 TO STA. 11+65	STALEY ROAD STA. 237+00 TO STA. 257+00
CURTIS STA. 11+65 TO STA. 42+90		STA. 297+20.45 (FAI 57) = STA. 28+20.30 (CURTIS ROAD)		STA. 42+90 TO STA. 51+03.29	WEST CURTIS STA. 40+00 TO STA. 1+10.60
IM 90% FED 10% STATE	100% CITY OF CHAMPAIGN	IM 90% FED 10% STATE	100% CITY OF CHAMPAIGN	STP 80% FED 10% CITY 10% COUNTY	
1000-2A		X781-2A		1000-2A	

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
2• 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240VOLT	EACH	1.0	1.0					
2• 83034400	LIGHT POLE, STEEL, 45 FT. M. H., TENON MOUNT	EACH	10.0	8.0				2.0	
2• 83035400	LIGHT POLE, STEEL, 45 FT. M. H., TENON MOUNT - TWIN	EACH	2.0	2.0					
2• 83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	10.0	8.0				2.0	
2• 83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	2.0	2.0					
2• 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	48.0	40.0				8.0	
• A2000610	TREE, ACER PLATANOIDES (NORWAY MAPLE), 1-1/4" CALIPER, BALLED AND BURLAPPED	EACH	6.0						6.0
• A2001010	TREE, ACER RUBRUM (RED MAPLE), 1-1/4" CALIPER, BALLED AND BURLAPPED	EACH	5.0						5.0
• A2001210	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 1-1/4" CALIPER, BALLED AND BURLAPPED	EACH	6.0						6.0
• A2002370	TREE, BETULA NIGRA (RIVER BIRCH), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	5.0						5.0
• A2003312	TREE, FRAXINUS AMERICANA (WHITE ASH), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8.0						8.0
• A2004212	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7.0						7.0
• A2006912	TREE, QUERCUS PALUSTRIS (PIN OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5.0						5.0
• A2007112	TREE, QUERCUS RUBRA (RED OAK), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5.0						5.0
• B2000412	TREE, ACER GRISEUM (PAPERBARK MAPLE), 1-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4.0						4.0
• D2002172	EVERGREEN, PICEA PUNGENS (COLORADO SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	4.0						4.0
• D2002272	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	11.0						11.0
X0321962	CONNECTION OF EXISTING PIPE UNDERDRAIN	EACH	8.0	8.0					
X0322729	MATERIAL TRANSFER DEVICE	TON	11,503.0	8,841.8				2,661.2	
X0324058	OUTLET SPECIAL	EACH	2.0						2.0
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SO YD	2,076.0		2,076.0				
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	12.0	12.0					
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	865.0						865.0
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	696.0						696.0
X4073071	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 9 1/2"	SO YD	2,460.0						2,460.0
X4073131	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 12 1/2"	SO YD	27,910.0	17,350.0				10,560.0	
X4073146	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13 1/4"	SO YD	17,738.0	17,738.0					

SPECIALTY ITEMS

- 1 SFTY-3N IMPACT ATTENUATORS
- 2 Y030-1E HIGHWAY ILLUMINATION 4 Y060 GAS MAIN--100% U OFI

ROADWAY WITHIN A/C	DETENTION WITHIN A/C	STRUCTURE WITHIN A/C	CSS FEATURES WITHIN A/C	FOUR-LANE OUTSIDE OF A/C	TWO-LANE OUTSIDE OF A/C
--------------------	----------------------	----------------------	-------------------------	--------------------------	-------------------------