

## SCHEDULES OF QUANTITIES

**44201771 CLASS D PATCHING, TYPE IV, 10"**

STATION	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE IV (SQ. YD.)
245+91.5	27.5	22.0	67.2
246+66	35.5	6.5	25.6
247+07	37.2	6.5	26.9
247+96	24.5	22.0	59.9
			179.6

USE = 180 SQ YD

**48300300 PORTLAND CEMENT CONCRETE SHOULDERS 8"**

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	SQ. YD.
CURTIS 26+65.30	LT	26+80.30	15.00	10.0	16.7
26+65.30	RT	26+80.30	15.00	10.0	16.7
29+60.30	LT	29+75.30	15.00	10.0	16.7
29+60.30	RT	29+75.30	15.00	10.0	16.7
					66.8

TOTAL = 66.8

USE = 67 SQ. YD.

**50105220 PIPE CULVERT REMOVAL**

STATION	FEET
W. CURTIS 41+08 RT.	16 18" RCP
CURTIS 0+59 RT.	24
13+28 RT.	24
19+94 LT.	23
26+15 RT.	24
40+17 LT.	16
STALEY 237+96 LT.	136 15" CMP
240+15 RT.	33 15" CMP
255+05 LT.	32 15" CMP
TOTAL = 328	

USE = 328 FEET

**50300130 PREFORMED JOINT SEAL 4"**

STATION	TO	STATION	LENGTH (FT)
26+80.3	45.0' LT.	26+80.3	35.0' LT.
26+80.3	11.0' LT.	26+80.3	11.0' RT.
26+80.3	35.0' RT.	26+80.3	45.0' RT.
29+60.3	45.0' LT.	29+60.3	35.0' LT.
29+60.3	11.0' LT.	29+60.3	11.0' RT.
29+60.3	35.0' RT.	29+60.3	45.0' RT.
			84.0

TOTAL = 84.0

USE = 84 FEET

**51500100 NAME PLATES**

STATION	CULVERT NO.	EACH
RAMP B 26+36	3	1
16+79.62	4	1
RAMP A 16+40.91	7	1
21+70	8	1
RAMP D 31+31.92	16	1
CURTIS 21+18.5	17	1
26+37.14	18	1
RAMP C 41+52.28	19	1
CURTIS 28+20.3	S. N. 010-0272	1
		9

TOTAL = 9

USE = 9 EACH

**54213447 END SECTION 12"**

STATION	OFFSET	EACH
CURTIS 26+72.8	161.0' LT.	1
26+72.8	161.0' RT.	1
29+67.8	153.0' RT.	1
29+67.8	150.0' LT.	1
RAMP A 25+00	30.7' RT.	1
RAMP B 9+25	30.7' RT.	1
RAMP C 45+00	30.7' RT.	1
RAMP D 25+10	25.1' RT.	1
		8

TOTAL = 8

USE = 8 EACH

**54213471 END SECTIONS 36"**

STATION	EACH
STALEY 237+21.17 LT.	1
238+56.61 LT.	1
TOTAL = 2	

USE = 2 EACH

**54213663 PRC FLARED END SECTION 18"**

STATION	EACH
CURTIS 43+98.25, 106.93' RT.	1

USE = 1 EACH

**54213669 PRC FLARED END SECTION 24"**

STATION	EACH
I-57 314+00 100' LT.	1

USE = 1 EACH

**54213693 PRC FLARED END SECTION 48"**

STATION	EACH
CURTIS 42+70.00 RT.	1

USE = 1

**54214293 END SECTIONS, EQUIVALENT ROUND-SIZE 18"**

STATION	EACH
STALEY 239+84.96 RT.	1
240+52.84 RT.	1
TOTAL = 2	

USE = 2 EACH

**54214305 END SECTIONS, EQUIVALENT ROUND-SIZE 30"**

STATION	EACH
STALEY 254+72.69 LT.	1
255+38.56 LT.	1
TOTAL = 2	

USE = 2 EACH

**54214503 PRC FLARED END SECTION EORS 18"**

STATION	EACH
CURTIS 36+69.50 RT.	1
37+00.50 RT.	1
TOTAL = 2	

USE = 2 EACH

**54248510 CONCRETE COLLAR**

STATION	CUL. YD.
I-57 314+00, 75' LT.	0.45

USE = 0.5 CU. YD.

**542A0229 PIPE CULVERT CLASS A, TYPE 1, 24"**

STATION	TO	STATION	FEET
I-57 314+00	75' LT.	314+00	100' LT.
			25

USE 25 FEET

**542A1063 PIPE CULVERTS, CLASS A, TYPE 2, 18"**

STATION	TO	STATION	FEET
CURTIS 43+73.94, 107.73' RT		43+98.25, 106.93' RT	24.32'

USE = 25 FEET

**542A1093 PIPE CULVERTS, CLASS A, TYPE 2, 48"**

STATION	TO	STATION	FEET
CURTIS 42+70.00, 118.04' RT.		43+73.94, 107.73' RT.	103.94

USE = 104 FEET

**542A5473 PIPE CULVERTS, CLASS A, TYPE 1, EORS 18"**

STATION	TO	STATION	FEET
CURTIS 36+67.61 RT.		37+01.59 RT.	34.0

USE = 34 FEET

**542D0241 PIPE CULVERTS, CLASS D, TYPE 1, 36"**

STATION	FEET
STALEY 237+96 LT.	136.0

USE = 136 FEET

**542D5473 PIPE CULVERTS, CLASS D, TYPE 1, EORS 18"**

STATION	FEET
STALEY 240+15 RT	68.0

USE = 68 FEET

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES