

SCHEDULES OF QUANTITIES

SIGNING SCHEDULE (CONT.)

PROPOSED LOCATION	SIGN DESCRIPTION	SIGN NO.	MUTCD	SIZE (IN X IN)	SIGN PANEL			SIGN SUPPORTS				
					TYPE 1	TYPE 2	TYPE 3	WOOD 4"x6"	CONCRETE FOUNDATIONS	STRUCTURAL STEEL		
					72000100 (SQ FT)	72000200 (SQ FT)	72000300 (SQ FT)	73000100 (FOOT)	73400100 (CU YD)	72700100 (POUND)	MEMBER*	
I-57 283+00 RT	CURTIS ROAD EXIT HERE	4	E5-1a (SEE DETAIL)	60"x90"			37.5	32.0				
I-57 285+30 LT	MERGE		W4-1(RIGHT)	48"x48"		16.0		18.0				
I-57 309+00 RT	MERGE		W4-1(RIGHT)	48"x48"		16.0		18.0				
I-57 311+20 RT	CURTIS ROAD EXIT HERE	5	E5-1a (SEE DETAIL)	60"x90"			37.5	32.0				
I-57 318+20 LT	CURTIS ROAD EXIT AHEAD	6	E1-2 (SEE DETAIL)	156"x126"			136.5		2.5	1352.0	W10 X 26 X 22' W10 X 26 X 24'	
I-57 327+00 RT	NORTH		M3-1(BL)	30"x15"	3.1			18.0				
I-57 327+00 RT	I-57		M1-1(2DIGIT)	36"x36"	9.0							
I-57 332+00 RT	SPEED LIMIT 65		R2-1(65)	48"x60"		20.0		20.0				
I-57 332+00 RT	MINIMUM 45		R2-1102(45)	48"x36"		12.0						
I-57 338+65 LT	CURTIS ROAD 1/2 MILE	7	E1-2 (SEE DETAIL)	156"x102"			110.5		1.4	702.0	W8 X 18 X 17.5' W8 X 18 X 16.5'	
I-57 365+05 RT	CURTIS ROAD 1 MILE	8	E1-2 (SEE DETAIL)	156"x102"			110.5		2.4	1012.0	W10 X 22 X 19' W10 X 22 X 21'	
RAMP A 11+50 RT	USE PROHIBITED		R5-1100	48"x60"				18.0				
RAMP B 9+00 RT	RAMP 50MPH		W13-3	48"x60"		20.0		18.0				
RAMP B 17+00 RT	STOP AHEAD		W3-1a	36"	9.0			18.0				
RAMP B 26+00 RT	WRONG WAY		R5-1A	36"x24"	6.0			12.0				
RAMP B 26+00 LT	WRONG WAY		R5-1A	36"x24"	6.0			12.0				
RAMP B 26+80 RT	DO NOT ENTER		R5-1	36"x36"	9.0			14.0				
RAMP B 26+80 LT	DO NOT ENTER		R5-1	36"x36"	9.0			14.0				
RAMP B 27+30 LT	STOP		R1-1	36"x36"	9.0			14.0				
RAMP B 27+30 CL	STOP		R1-2	36"x36"	9.0			14.0				
RAMP B 27+30 RT	STOP		R1-3	36"x36"	9.0			14.0				
RAMP B 27+30 LT	ONE WAY		R6-1(LEFT)	36"x12"	3.0							
RAMP B 27+30 RT	ONE WAY		R6-1(LEFT)	36"x12"	3.0							
RAMP C 31+50 RT	USE PROHIBITED		R5-1100	48"x60"		20.0		18.0				
RAMP D 24+60 RT	RAMP 50MPH		W13-3	48"x60"		20.0		18.0				
RAMP D 32+00 RT	STOP AHEAD		W3-1a	36"	9.0			18.0				
RAMP D 41+00 RT	WRONG WAY		R5-1a	36"x24"	6.0			12.0				
RAMP D 41+00 LT	WRONG WAY		R5-1a	36"x24"	6.0			12.0				
RAMP D 41+80 RT	DO NOT ENTER		R5-1	36"x36"	9.0			14.0				
RAMP D 41+80 LT	DO NOT ENTER		R5-2	36"x36"	9.0			14.0				
RAMP D 42+30	STOP		R1-1	36"x36"	9.0			14.0				
RAMP D 42+30	STOP		R1-1	36"x36"	9.0			14.0				
RAMP D 42+30	STOP		R1-1	36"x36"	9.0			14.0				
RAMP D 42+30	ONE WAY		R6-1(LEFT)	36"x12"	3.0							
RAMP D 42+30	ONE WAY		R6-1(LEFT)	36"x12"	3.0							
TOTALS WITHIN ACCESS CONTROL LIMITS					231.6	176.0	1,398.0	598.0	23.3	11,678.0		

TOTALS	366.0	176.0	1,398.0	812.0	26.0	12,923.0
UNIT	(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)	(CU YD)	(POUND)
PAY ITEM	72000100	72000200	72000300	73000100	73400100	72700100

* REQUIRED LENGTHS OF STRUCTURAL STEEL MEMBERS SHALL BE FIELD VERIFIED BEFORE ORDERING.
 ** ADDENDUMS IN BOLD AND ITALIC; 5/21/2006

70400100 TEMPORARY CONCRETE BARRIER		
STATION	TO	STATION
I-57 OUTSIDE SHOULDER		
NB 293+70		297+80
SB 296+60		300+70
		410
		410
I-57 INSIDE SHOULDER		
NB 292+70		297+80
SB 296+60		301+70
		510
		510
TOTAL = 1,840		

USE = 1,840 FEET

73700200 REMOVE CONCRETE FOUNDATION - GROUND MOUNT		
STATION		EACH
I-57 STA. 297+62.7, 95.7 RT.		1

USE = 1 EACH