

## SCHEDULES OF QUANTITIES

### LIGHTING SCHEDULE

PROPOSED LOCATION	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	LIGHT POLE STEEL, 45' M. H. TENON MOUNT	LIGHT POLE STEEL, 45' M. H. TENON MOUNT - TWIN	LIGHT POLE FOUNDATION, METAL, 15" B. C., 8" X 6'	LIGHT POLE FOUNDATION, METAL, 15" B. C., 8" X 8'	BREAKAWAY DEVICE, COUPLING, SS SCREEN
	82103900 (EACH)	83034400 (EACH)	83035400 (EACH)	83600355 (EACH)	83600357 (EACH)	83800650 (EACH)
CURTIS 5+00 LT	1	1		1		4
CURTIS 21+75 LT	2		1		1	4
CURTIS 34+50 RT	2		1		1	4
CURTIS 48+25 RT	1	1		1		4
RAMP B 7+00 RT	1	1		1		4
RAMP B 9+00 RT	1	1		1		4
RAMP B 11+00 RT	1	1		1		4
RAMP B 13+00 RT	1	1		1		4
RAMP D 23+00 RT	1	1		1		4
RAMP D 25+00 RT	1	1		1		4
RAMP D 27+00 RT	1	1		1		4
RAMP D 29+00 RT	1	1		1		4
<b>TOTALS</b>	<b>14.0</b>	<b>10.0</b>	<b>2.0</b>	<b>10.0</b>	<b>2.0</b>	<b>48.0</b>
<b>UNIT</b>	<b>(EACH)</b>	<b>(EACH)</b>	<b>(EACH)</b>	<b>(EACH)</b>	<b>(EACH)</b>	<b>(EACH)</b>
<b>PAY ITEM</b>	<b>82103900</b>	<b>83034400</b>	<b>83035400</b>	<b>83600355</b>	<b>83600357</b>	<b>83800650</b>

### LIGHTING SCHEDULE (CONTINUED)

LOCATION	CONDUIT, FLEX. NON-METALLIC, WEATHERPRF, 2"	CONDUIT IN TRENCH, 2" DIA, INTER. METAL	CONDUIT PUSHED, 2" DIA, INTER. METAL	CONDUIT PUSHED, 3" DIA, INTER. METAL	CONDUIT EMBEDDED IN STRUCTURE, 2" PVC	JUNCTION BOX, 18" X 12" X 6"	TRENCH AND BACKFILL FOR ELECTRICAL WORK	UNIT DUCT #8	UNIT DUCT #6	UNIT DUCT #4	UNIT DUCT #2	ELEC. CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3 1/C #2
	#5000780 (EACH)	81014600 (FOOT)	81020500 (FOOT)	81020700 (FOOT)	81200230 (FOOT)	81300800 (EACH)	81500200 (FOOT)	81600215 (FOOT)	81600315 (FOOT)	81600415 (FOOT)	81600515 (FOOT)	81702400 (FOOT)
CURTIS 5+00 LT TO 21+76 LT							1708.7			1708.7		
21+76 LT TO 26+90 LT							524.3				524.3	
26+90 LT TO 29+56 LT					535.0							256.0
26+90 RT TO 29+56 RT					535.0							
29+56 LT TO 29+56 RT			100.0				89.8				89.8	
29+56 RT TO 34+50 RT							515.6					515.6
34+50 RT TO 35+59 RT							140.4					140.4
35+59 RT TO 48+25 RT							1272.7	1280.0				
RAMP B 7+00 RT TO 27+00 RT			50.0				2004.1		2010.0			
RAMP D 23+00 RT TO 42+23 LT				50.0			1944.1			1944.1		
CURTIS 26+90 LT	1.0	8.0				1.0						8.0
26+90 RT	1.0	8.0				1.0						
29+50 LT	1.0	8.0				1.0						8.0
29+50 RT	1.0	8.0				1.0						8.0
<b>TOTALS</b>	<b>4.0</b>	<b>32.0</b>	<b>150.0</b>	<b>50.0</b>	<b>1070.0</b>	<b>4.0</b>	<b>8200.0</b>	<b>1280.0</b>	<b>2010.0</b>	<b>3655.0</b>	<b>1275.0</b>	<b>280.0</b>
<b>UNIT</b>	<b>(EACH)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(EACH)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>	<b>(FOOT)</b>
<b>PAY ITEM</b>	<b>#5000780</b>	<b>81014600</b>	<b>81020500</b>	<b>81020700</b>	<b>81200230</b>	<b>81300800</b>	<b>81500200</b>	<b>81600215</b>	<b>81600315</b>	<b>81600415</b>	<b>81600515</b>	<b>81702400</b>

### STORM SEWER STRUCTURE SCHEDULE

STR. NO.	STRUCTURE TYPE	CL OF STR. STATION	CL OF STR OFFSET	CL OF 2' OPENING STATION	CL OF 2' OPENING OFFSET	EX. T/O FRAME & GRATE ELEV.	PR. T/O FRAME & GRATE ELEV.	EX. T. O. M. ELEV.	PR. T. O. M. ELEV.	INVERT IN ELEV.	INVERT OUT ELEV.
100	INLET TB T1F OL	25+00.00	18.3' LT	25+00.00	18.3' LT	----	701.709	----	700.959	698.850	695.868
101	INLET TB T1F OL	9+25.00	19.3' LT	9+25.00	19.3' LT	----	701.140	----	700.390	----	696.086
102	INLET TB T1F OL	45+00.00	18.2' LT	45+00.00	18.2' LT	----	700.743	----	699.993	----	694.890
103	INLET TB T1F OL	25+10.00	20.0' LT	25+10.00	20.0' LT	----	701.343	----	700.593	----	697.217
134	MAN RECON W/ NEW T1F, CL	43+73.94	107.7' RT	43+75.94	107.7' RT	706.830	708.516	705.830	707.516	702.170	699.160
										699.530	