3/31/2006

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	10-32HB-3,K	CHAMPAIGN	352	48
STA. 32+00	TO STA. 38+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 90758

1"=20'
0' 5' 10' 15' 20' 40' 60'

SEC. 28, T. 19 N., R. 8 E., 3rd P.M.

SEE DETAIL "LOCATION & DESIGN OF BLOCKOUTS FOR SIGN POSTS"

STA. 35+06.49 (CURTIS ROAD) =
STA. 10+00.00 (RAMP A) =
STA. 27+81.35 (RAMP B)

PROPOSED CULVERT #2
CAST IN PLACE REINFORCED CONCRETE BOX CULVERT, 4'x3' - 223.2 FEET
STA. 36+46.82, 113.47' LT., U.S.F.L. = 696.79
STA. 36+46.82, 109.73' RT., D.S.F.L. = 695.92
NO SKEW
PRECAST OPTION NOT ALLOWED

N

EXISTING R.O.W. LINE
RAMP A
RAMP B
℄ CURTIS ROAD
ABANDONED
SEE LAYOUT DETAIL
EXISTING R.O.W. LINE
EXISTING R.O.W. LINE
EXISTING R.O.W. LINE

PLAN
SURVEYED
DRAWN
ALIGNMENT CHECKED
TYP. SECT. W/ CHECKED
NOTE BOOK
NO.
DATE
BY

SEE INTERSECTION DETAILS

SEC. 33, T. 19 N., R. 8 E., 3rd P.M.

950.00' v.c.
600.00' v.c.

SEE SIGNING PLANS FOR DETAILS
SEE LIGHTING PLANS FOR DETAILS
SEE GAS PIPELINE PLANS FOR DETAILS

PROP. RIGHT DITCH
PROP. LEFT DITCH

+0.68% +10.00 EL. 695.29 +0.23% +0.68% +0.23% +00.00 EL. 696.90 -0.24% +46.80 EL. 696.79 +0.74% +0.32% +95.00 EL. 695.71 +0.32% +67.61 EL. 695.54 +0.47% +01.53 EL. 696.10 +0.48%

	RIGHT DITCH ELEV.	LEFT DITCH ELEV.	CENTERLINE ELEVATIONS
32+00	693.86		698.10 722.72
32+50	694.20		698.17 722.47
33+00	694.54		698.26 722.22
33+50	694.88		698.35 721.95
34+00	695.22		698.45 721.67
34+50	695.38		698.53 721.37
35+00	695.49		698.62 721.07
35+50	695.61		698.81 720.77
36+00	695.73	696.90	698.99 720.47
36+50	695.88	696.81	699.16 720.17
37+00	696.09	697.18	699.28 719.87
37+50	697.55		699.42 719.57
38+00	697.92		699.57 719.27
			699.70 718.97
			699.82 718.67
			699.98 718.37
			700.15 718.07
			700.29 717.77
			700.51 717.47
			700.67 717.17
			700.74 716.87
			700.84 716.57
			700.90 716.27
			700.96 715.97
			701.02 715.67
			701.12 715.37
			701.24 715.07
			701.34 714.77
			701.43 714.48
			701.57 714.21
			701.67 713.97

PROFILE
SURVEYED
DRAWN
GRADES CHECKED
STAK. NOTES
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.
DATE
BY

ILLINOIS DEPARTMENT OF TRANSPORTATION

CURTIS ROAD PLAN & PROFILE

c:\projects\d505095\pp20.dgn