



CONSTRUCTION NOTES:

Maintain 5' Minimum Depth (top of Pipe) Below G.L. →

Abandon Pipe Will Be Grouted

Begin Transition from 5' Minimum Depth to 8' Minimum Depth (top of Pipe) Below G.L. →

Sta. 19+00 - Begin 8' Minimum depth (top of pipe) Below G.L. →

LEGEND:

UIUC 8" GAS LINE ———— (U) 8" ————

GROUND LEVEL DEPTH (Surface) ———— GL ELEV ————

PROPOSED GAS LINE (Top of Pipe) ———— Prop Gas ————

MATERIALS:

MKT NO.	QTY.	DESCRIPTION
1	1102'	8" Steel Pipe - 8.625" O.D., 250 wall, API 5L, Grade B Fusion Bonded Epoxy Coated

MATERIALS:

MKT NO.	QTY.	DESCRIPTION



Revisions

19-Oct-05	SDP	
23-Nov-05	SDP	

Utility Safety & Design, Inc.
 #9 Executive Woods Court Suite 1
 Belleville, Illinois
 Relocate UI Lateral
 Natural Gas Pipeline for
 Phase 2 of Curtis Road Improvements
 Station 10+00 to Station 21+00 | U2

Scale: 1" = 40'