

CONTRACT NO. 90758									
FED.	FED. ROAD DIST. NO. ILLIN			015	FED. AID	PROJECT			
STA	STA. TO STA.								
57		10-32HB-3 , К		Champaign		352	165		
F.A.I RTE.		SECTION		COUNTY		TOTAL SHEETS	SHEET NO.		

BILL OF MATERIAL (ONE HEADWALL)

Bar	No.	Size	Length (ft)	Shape
b	1	#4	14'-11''	
b,	1	#4	17'-5''	—
b ₂	1	#4	19'-11''	
D3	2	#4	21'-11''	
h	1	#4	27'-3''	
h,	2	#4	7'-0''	
h ₂	2 2 2 2 2 2 2 2 2 2 2 2 2 2	#4	6'-10''	
S	2	#4	34'-8''	
Vi	2	#4	5'-10''	L
V ₂	2	#4	5'-2''	L
∨3	2	#4	4'-10''	
V4	2	#4	4'-5''	
V5	2	#4	4'-1''	
V6	2	#4	3'-8'' 3'-4''	L
V7	2	#4	3'-4''	L
W	8	#4	7'-4''	٦
Wj	2 2 2	#4	7'-1''	٦
W ₂	2	#4	5'-7''	Γ
W3	2	#4	4'-1''	٦
Reinfo		252		
Class	wall. CU. YD.	5.8		
	ITE	UNIT	QUANT.	
	Culver Culve		2	

BOX CULVERT END SECTIONS (CAST IN PLACE) 1 @ 10.0' X 2' STA. 245+91.59 NO SKEW

REINEO	RCED	CONCRETE HEADWALL DETAILS					
	INCED	CONCRETE HEADWALE DETAILS					
REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION					
NAME	DATE						
		CULVERT DETAILS					
		ULVENI DETAILO					
		SCALE: VERT. DRAWN BY JDC					
		HORIZ.					
		DATE 110904 CHECKED BY					