CONTRACT NO. 94976

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 70 | (25-3,4)RS-2 | EFFINGHAM | 25 | 4 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SUMMARY OF QUANTITIES

| | CODE NO | ITEM | UNIT | TOTAL QUANTITIES | URBAN CONSTRUCTION TYPE CODE 1000 90% FED. 10% STATE |
|---|---|---|---|---|---|
| | 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 19153 | 19153 |
| | 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 |
| | 44000007 | BITUMINOUS SURFACE REMOVAL 2" | SQ YD | 191531 | 191531 |
| | 44201043 | CLASS B PATCHES, TYPE II, 16 INCH | SQ YD | 275 | 275 |
| | 44213200 | SAW CUTS | FOOT | 1588 | 1588 |
| * | 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 325 | 325 |
| * | 63100085 | TRAFFIC BARRIER TERMINAL, TYPE 6 | EACH | 1 | 1 |
| | 63200310 | GUARDRAIL REMOVAL | FOOT | 325 | 325 |
| | 67000500 | ENGINEER'S FIELD OFFICE, TYPE B | CAL MO | 2 | 2 |
| | 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| | 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 2816 | 2816 |
| | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 134620 | 134620 |
| | 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 17640 | 17640 |
| | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 3258 | 3258 |
| | 78003130 | PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6" | FOOT | 17640 | 17640 |
| * | 78005110 | EPOXY PAVEMENT MARKING - LINE 4" | FOOT | 134620 | 134620 |
| * | 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 1765 | 1765 |
| * | 88600100 | DETECTOR LOOP, TYPE I | FOOT | 184 | 184 |
| | X0322729 | MATERIAL TRANSFER DEVICE | TON | 21451 | 21451 |
| | X4066540 | POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N105 | TON | 21451 | 21451 |
| | X7010805 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL) | L SUM | 1 | 1 |
| | X7011420 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 | L SUM | 1 | 1 |
| | X7015000 | CHANGEABLE MESSAGE SIGN | CAL MO | 18 | 18 |
| | Z0017100 | DOWEL BARS | EACH | 680 | 680 |
| ⊙ | Z0076600 | TRAINEES | HOUR | 1000 | 1000 |

⊙ YOBO

* SPECIALTY ITEMS

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 3/30/2006
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = district