

DRAINAGE SCHEDULE

FROM	OFFSET (FEET)	TO STATION	OFFSET (FEET)	STORM SEWER TYPE	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	SIZE & LENGTH OF PIPE (FEET)	PRECAST REINF. CONC. FLARED END SEC. (EACH)	PIPE CULVERT REMOVAL (FEET)	PRECAST REINF. CONC. FLARED END SEC. (EACH)	TRENCH BACKFILL (CU YD)
					12"	12"	15"	15"	18"	18"	24"	36"	24"	36"		
SEIBERT ROAD																
3+11.00	16.25	RT	3+69.54	14.84	RT	CLASS A, TYPE 1	58.0									10.9
3+11.00	12.88	LT	3+63.01	13.01	LT	CLASS A, TYPE 1	52.0									8.2
3+11.00	12.88	LT	3+11.00	16.25	RT	CLASS A, TYPE 1	29.0									3.8
3+50.00	38.47	RT	3+93.24	30.25	RT	CLASS A, TYPE 1										9.9
3+69.54	14.84	RT	3+93.24	30.25	RT	CLASS A, TYPE 1			27.0				40.0			6.8
3+93.24	30.25	RT	4+95.84	14.08	RT	CLASS A, TYPE 1					95.0					23.4
4+95.84	14.08	RT	5+35.00	13.00	RT	CLASS A, TYPE 1					37.0					8.0
5+35.00	13.00	LT	5+35.00	13.00	RT	CLASS A, TYPE 1	26.0									5.9
5+35.00	13.00	RT	5+80.00	13.00	RT	CLASS A, TYPE 1			43.0							7.7
5+80.00	13.00	RT	6+24.00	13.00	RT	CLASS A, TYPE 1	42.0									5.8
6+24.00	13.00	RT	6+24.00	13.00	LT	CLASS A, TYPE 1	26.0									3.5
7+33.85	13.14	RT	7+33.85	13.00	LT	CLASS A, TYPE 2			26.0							9.9
7+33.85	13.14	RT	8+87.85	13.00	RT	CLASS A, TYPE 2			154.0							104.2
8+87.85	13.00	RT	10+41.93	13.00	RT	CLASS A, TYPE 1	154.0									51.0
10+41.93	13.00	RT	11+13.73	15.51	RT	CLASS A, TYPE 1	74.0									17.3
10+41.93	13.00	LT	11+52.06	13.00	LT	CLASS A, TYPE 1	107.0									72.4
11+13.73	15.51	RT	11+29.23	36.22	RT	CLASS A, TYPE 2					26.0					23.2
11+29.23	36.22	RT	11+87.20	15.20	RT	CLASS A, TYPE 2					64.0					45.6
11+52.06	13.00	LT	12+42.05	13.00	LT	CLASS A, TYPE 2			88.0							59.5
11+17.00	33.00	RT	11+17.00	50.00	RT									10		3.5
11+87.20	15.20	RT	12+92.51	13.00	RT	CLASS A, TYPE 1							108.0			36.7
12+42.05	13.00	LT	12+92.51	13.00	LT	CLASS A, TYPE 1	49.0									33.1
12+92.51	13.00	RT	14+00.00	13.00	RT	CLASS A, TYPE 1							107.0			32.5
12+92.51	13.00	LT	14+00.00	13.00	LT	CLASS A, TYPE 2			108.0							73.5
14+00.00	13.00	RT	14+00.00	13.00	LT	CLASS A, TYPE 1					26.0					17.8
14+00.00	13.00	RT	14+60.00	13.00	RT	CLASS A, TYPE 1					60.0					47.8
14+00.00	13.00	RT	14+00.00	163.00	RT	CLASS A, TYPE 1							150.0		1	23.1
14+60.00	13.00	RT	14+60.00	13.00	LT	CLASS A, TYPE 1	26.0									17.5
14+60.00	13.00	RT	15+80.00	13.00	RT	CLASS A, TYPE 1					120.0					43.8
15+80.00	13.00	RT	15+80.00	13.00	LT	CLASS A, TYPE 1	26.0									6.1
13+19.00	2.00	LT	13+19.00	40.00	RT									42		19.5
17+11.47	15.00	RT	P.E.													
TOTAL:					669	268	70	108	338	90	255	150	1	52	1	831.8

MANHOLE AND INLET SCHEDULE

STATION	OFFSET (FEET)	MH T-A 4" DIA. T-24 F&G	INLET		MH TYPE A 5' T-24 F&G	MH TYPE A 6' T-24 F&G	FLOWLINE	INVERT
			TYPE-A T-24 F&G	TYPE-B T-24 F&G				
SEIBERT RD.								
3+11.00	12.88	LT					660.05	656.97
3+11.00	16.25	RT					660.01	656.88
3+63.01	13.01	LT	1				660.80	657.13
3+69.54	14.84	RT		1			660.46	656.27
3+93.24	30.25	RT			1		660.49	656.15
4+95.84	14.08	RT	1				660.58	656.43
5+35.00	13.00	LT		1			660.89	656.66
5+35.00	13.00	RT	1				660.41	656.55
5+80.00	13.00	RT			1		660.08	656.67
6+24.00	13.00	LT		1			660.21	656.87
6+24.00	13.00	RT			1		659.73	656.79
7+33.85	13.14	RT			1		658.90	652.90
7+33.85	13.00	LT		1			658.90	653.90
8+87.85	13.00	RT			1		657.56	651.56
10+41.93	13.00	RT			1		654.33	650.28
10+41.93	13.00	LT		1			654.33	648.33
11+13.73	15.51	RT	1				652.22	645.08
11+29.23	36.22	RT			1		652.00	645.00
11+52.06	13.00	LT			1		651.00	645.00
11+87.20	15.20	RT	1				649.87	644.80
12+42.05	13.00	LT			1		648.74	642.74
12+92.51	13.00	RT	1				647.86	642.86
12+92.51	13.00	LT			1		647.86	641.86
14+00.00	13.00	RT				1	646.80	638.80
14+00.00	13.00	LT	1				646.80	640.91
14+60.00	13.00	RT			1		646.31	640.10
14+60.00	13.00	LT		1				
15+80.00	13.00	LT			1		644.61	640.54
15+80.00	13.00	RT	1				644.61	640.46
TOTAL		7	7	12	2	1		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES SEIBERT ROAD SECTION 00-00007-01-PV ST. CLAIR COUNTY
NAME	DATE	

SCALE: VERT. _____ DRAWN BY _____
HORIZ. _____ CHECKED BY _____
DATE _____