

CONTRACT NO. 97279

PAVING SCHEDULE

LOCATION	AGG BASE CSE TA TON	BIT. CONC. BINDER TON	BIT. SURF. CSE TON
STA. 27+10 TO STA. 27+60.25	11	17	
STA. 29+11.75 STA. 29+36.07	11	8	
STA. 26+60 TO STA. 29+58.07			81
TOTAL	22	25	81

MIXTURE REQUIREMENTS -- SUPERPAVE PROJECT

MIXTURE USE	SURFACE	BINDER
AC/PG	PG 64-22	PG 64-22
RAP % (MAX)	0	0
DESIGN AIR VOIDS	4.0% @ Ndes=50	4.0% @ Ndes=50
MIX COMPOSITION (GRADATION MIXTURE)	9.5	IL 19.0
FRICITION AGG	MIXTURE C	MIXTURE B

