

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	60	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
* [X1-(4,4-1,5,6,6-2)] R-1				

RESURFACING AND SHOULDER SCHEDULE (I-57 NORTHBOUND)

LOCATION STATION TO STATION	RUBBLIZE PCC PAVEMENT	POLYMERIZED BIT CONCRETE BINDER COURSE	POLYMERIZED BIT CONCRETE SURFACE COURSE	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	SUB-BASE GRANULAR MATERIAL, TYPE A	BITUMINOUS MATERIALS PRIME COAT	SHOULDERS		BITUMINOUS SHOULDERS 13 3/4"	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS SURFACE REMOVAL 4"	SHOULDER RUMBLE STRIP	TEMPORARY RAMP	BIT SURFACE REMOVAL BUTT JOINT
								AGGREGATE TYPE B	BITUMINOUS (SUPERPAVE)						
	SQ YD	TONS	TONS	SQ YD	SQ YD	TONS	GAL	TONS	TONS	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	SQ YD
NORTHBOUND															
287+46.45 TO 289+26.45		16	54				72	12	58				360	59	356
289+26.45 TO 0+00															
0+00 TO 57+43.55	15316	5826	1728				7454	727	2573			15529	11487		
57+43.55 TO 57+46.55															
57+46.55 TO 79+50	5876	2235	673				2868	279	987			5957	4407		89
79+50 TO 83+70		804	216	1120	1027	1595	953	54		747			1680	119	356
83+70 TO 157+95.58	19802	7532	2243				9645	940	3327			20077	14851		89
157+95.58 TO 157+96.05															
157+96.05 TO 163+40	1451	552	174				714	69	244			1471	1088		89
163+40 TO 168+10		883	186	1254	1149	1785	1022	60		836			1880	59	178
168+10 TO 193+20														74	444
193+20 TO 226+30	8827	6165	1006				4304	419	4120			8949	6620		89
226+30 TO 228+18		361	101	502	460	714	430	24		334			752	59	178
228+18 TO 229+15															
229+15 TO 231+50		448	115	627	621	893	529	30		418			940	59	178
231+50 TO 253+10	5760	2191	670				2819	274	968			5840	4320		178
253+10 TO 257+25		795	214	1107	1015	1576	943	53		738			1660	119	356
257+25 TO 347+00.75	23935	9105	2710				11657	1136	4022			24268	17952		89
347+00.75 TO 348+43.15															
348+43.15 TO 361+50	3485	1326	403				1704	166	586			3533	2614		89
361+50 TO 365+30		730	204	1014	929	1443	869	49		676			1520	119	356
365+30 TO 419+74.18	14518	5522	1647				7073	689	2439			14719	10888		89
419+74.18 TO 1461+00															
1461+00 TO 1465+00	1067	406	120				519	51	179			1081	800		
1465+00 TO 1466+80		16	54				72	12	58				360	89	356
JOHNSTON CITY ENTRANCE RAMP															
149+64.0 TO 155+79.0		266	133				154				1187				
155+79.0 TO 157+60.0		63	32				72	7	69						
157+60.0 TO 158+50.0		13	16				34	11	25			140		29	
TOTALS	100035	45254	12698	5624	5201	8006	53907	5063	19656	3748	1609	101425	84179	784	3556

PLOT DATE = 4/17/2006
 FILE NAME = c:\p\mets\jrb\1685\1685schu32
 PLOT SCALE = 80,0000 / IN.
 USER NAME = thomasht