

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	60	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

* [X1-(4,4-1,5,6,6-2)] R-1

PAVEMENT MARKING SCHEDULE (I-57 MAINLINE)

LOCATION STATION TO STATION	PREFORMED LINE 6" SKIP DASH WHITE FOOT	PREFORMED PAVEMENT MARKING			TEMPORARY PAVEMENT MARKING				SHORT TERM PAVEMENT MARKING (WHITE)		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKERS EACH	PAVEMENT MARKING REMOVAL FOOT	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	
		LINE 4" SOLID WHITE FOOT	SOLID YELLOW FOOT	LINE 8" SOLID WHITE FOOT	LINE 4"		LINE 8"		SKIP DASH FOOT	EDGE FOOT					
					SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT							
NB MAINLINE															
287+46.45 TO 289+26.45	45	180	180		180	45	180			16	14	2	2		10
289+26.45 TO 0+00	1436	5744	5744							2089	230	72	72		
0+00 TO 57+43.55															
57+43.55 TO 57+46.55															
57+46.55 TO 79+50	551	2203	2203							801	88	28	28		
79+50 TO 83+70	105	420	420		420	105	420			76	34		5	140	11
83+70 TO 157+95.58	1856	7426	7426							2700	297	93	93		
157+95.58 TO 157+96.05															
157+96.05 TO 163+40	136	544	544							198	22	7	7		
163+40 TO 168+10	118	470	470		470	118	470			85	38		6	157	13
168+10 TO 193+20															
193+20 TO 226+30	828	3310	3310							1204	132	41	41		
226+30 TO 228+17	47	187	187		187	47	187			34	15		2	62	5
228+17 TO 229+15															
229+15 TO 231+50	59	235	235		235	59	235			43	19		3	78	6
231+50 TO 253+10	540	2160	2160							785	86	27	27		
253+10 TO 257+25	104	415	415		415	104	415			75	33		5	138	11
257+25 TO 347+00.75	2244	8976	8976							3264	359	112	112		
347+00.75 TO 348+43.15															
348+43.15 TO 361+50	327	1307	1307							475	52	16	16		
361+50 TO 365+30	95	380	380		380	95	380			69	30		5	127	10
365+30 TO 419+74.18	1361	5444	5444							1980	218	68	68		
419+74.18 TO 1461+00															
1461+00 TO 1465+00	100	400	400							145	16	5	5		
1465+00 TO 1466+80	45	180	180		180	45	180			16	14	2	2		10
JOHNSTON CITY ENTRANCE RAMP															
151+25.0 TO 155+79.0	114					114				83					28
155+79.0 TO 158+50.0		271			271						22				7
	10108	40251	39980	271	271	730	2467	271		14139	1720	473	500	702	111
		80231			5934				15859						

NOTES:
 RAMP MARKING QUANTITY REFLECTS ONE APPLICATION EACH OF SHORT TERM PAVEMENT MARKING AND TEMPORARY PAVEMENT MARKING.
 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL SHALL BE INCLUDED IN THE COST OF PAVEMENT REMOVAL WHERE APPLICABLE.

PLOT DATE = 4/17/2005
 FILE NAME = c:\p\reports\9801680\9801680sh-02
 PLOT SCALE = 50,000 / IN.
 USER NAME = thomshf