

district
 3/23/2006
 c:\projects\94909d\05203pa.d

CONTRACT NO. 98980				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
853	9RS-4	HAMILTON	12	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 80% FED. 20% STATE		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	87	87		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3790	3790		
40600300	AGGREGATE (PRIME COAT)	TON	76	76		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	125	125		
40600990	TEMPORARY RAMP	SQ YD	82	82		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	32230	32230		
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	67	67		
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	20	20		
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	41	41		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	594	594		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4107	4107		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37091	37091		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	40	40		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	457	457		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3628	3628		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40	40		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	33463	33463		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	172	172		
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	TON	3184	3184		
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	1584	1584		
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	5542	5542		
XX005223	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N90	TON	136	136		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE: DRAWN BY: CHECKED BY:

PLOT DATE = 3/23/2006
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#