SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5KV UG CABLE IN UD	LF	5600	
AR110014	4" DIRECTIONAL BORE	LF	50	
AR125410	MITL-STAKE MOUNTED	EA	42	
AR125415	MITL-BASE MOUNTED	EA	8	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EA	1	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EA	2	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA	42	
AR125902	REMOVE BASE MOUNTED LIGHT	EA	8	
AR125904	REMOVE TAXI GUIDANCE SIGN	EA	3	
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR150540	HAUL ROUTE	LS	1	
AR156511	DITCH CHECK	EA	2	
AR156520	INLET PROTECTION	EA	3	
AR201660	BITUMINOUS CRACK REPAIR	LF	2812	
AR401610	BITUMINOUS SURFACE COURSE	TON	1246	
AR401620	BIT. SURFACE COURSE, LEVELING	TON	800	
AR401655	BUTT JOINT CONSTRUCTION	SY	1778	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	489	
AR402622	POROUS FRICTION COURSE, 0.10'	SY	10,389	
AR501900	REMOVE PCC PAVEMENT	SY	29	
AR510510	TIE DOWN	EA	16	
AR510900	REMOVE TIE DOWN	EA	24	
AR603510	BITUMINOUS TACK COAT	GAL	4848	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	3820	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	588	
AR705410	POROUS BACKFILL	CY	224	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	LF	1339	
AR705630	UNDERDRAIN INSPECTION HOLE	EA	5	
AR751909	REMOVE INSPECTION HOLE	EA	3	
AR751949	ADJUST INSPECTION HOLE	EA	9	
AR901510	SEEDING	AC	1.4	
AR905520	TOPSOILING (FROM OFF SITE)	CY	440	
AR908510	MULCHING	AC	1.4	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES, INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED PAVEMENT PREPARATION PLAN STA. 4+00 TO STA. 12+00
5	PROPOSED PAVEMENT PREPARATION PLAN STA. 12+00 TO STA. 20+00
6	PROPOSED PAVEMENT PREPARATION PLAN STA. 20+00 TO STA. 26+00
7	PROPOSED TYPICAL SECTIONS
8	PROPOSED PLAN AND PROFILE TAXIWAY B STA. 7+00 TO STA. 21+00
9	PROPOSED PLAN AND PROFILE TAXIWAY B STA. 21+00 TO STA. 24+81.11
10	PROPOSED PLAN AND PROFILE TAXIWAY C STA. 100+00 TO STA. 102+96.21
11	PROPOSED STAKING PLAN STA. 4+00 TO STA. 12+00
12	PROPOSED STAKING PLAN STA. 12+00 TO STA. 20+00
13	PROPOSED STAKING PLAN STA. 20+00 TO STA. 26+00
14	PROPOSED DRAINAGE PLAN
15	UNDERDRAIN NOTES AND DETAILS
16	PROPOSED STORMWATER POLLUTION PREVENTION PLAN
17	EXISTING TIE DOWN REMOVAL AND MARKING PLAN
18	PROPOSED MARKING PLAN STA 4+00 TO STA. 12+00
19	PROPOSED MARKING PLAN STA. 12+00 TO STA. 20+00
20	PROPOSED MARKING PLAN STA. 20+00 TO STA. 26+00
21	EXISTING ELECTRICAL PLAN STA. 4+00 TO STA. 12+00
22	EXISTING ELECTRICAL PLAN STA. 12+00 TO STA. 20+00
23	EXISTING ELECTRICAL PLAN STA. 20+00 TO STA. 26+00
24	PROPOSED ELECTRICAL PLAN STA. 4+00 TO STA. 12+00
25	PROPOSED ELECTRICAL PLAN STA. 12+00 TO STA. 20+00
26	PROPOSED ELECTRICAL PLAN STA. 20+00 TO STA. 26+00
27	ELECTRICAL DETAILS
28	ELECTRICAL DETAILS
29	ELECTRICAL NOTES
30	ELECTRICAL NOTES
31	PROPOSED APRON CROSS-SECTIONS STA. 7+02.28 TO STA. 7+18.12
32	PROPOSED APRON CROSS-SECTIONS STA. 7+50 TO STA. 8+00
33	PROPOSED APRON CROSS-SECTIONS STA. 8+50 TO STA. 9+00
34	PROPOSED APRON CROSS-SECTIONS STA. 9+29.35 TO STA. 9+64.87
35	PROPOSED APRON CROSS-SECTIONS STA. 9+79.35 TO STA. 10+19.35
36	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 10+21.20 TO STA. 10+71.20
37	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 11+00 TO STA. 12+50
38	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 12+97.64 TO STA. 13+47.72
39	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 14+22.72 TO STA. 15+00
40	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 15+50 TO STA. 17+00
41	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 17+50 TO STA. 18+50
42	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 19+00 TO STA. 20+50
43	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 21+00 TO STA. 22+50
44	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 23+00 TO STA. 24+22.63
45	PROPOSED TAXIWAY "B" CROSS-SECTIONS STA. 24+50 TO STA. 24+81.11
46	PROPOSED TAXIWAY "C" CROSS-SECTIONS STA. 100+30 TO STA. 101+00
47	PROPOSED TAXIWAY "C" CROSS-SECTIONS STA. 101+50 TO STA. 102+96.21

DATE	REVISION	BY

KEWANEE MUNICIPAL AIRPORT
KEWANEE, HENRY COUNTY, ILLINOIS

IL PROJ.: EZI-3533 A.I.P. PROJ.: 3-17-0058-B10

HBI Project No. 810-06TXYD 0800
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 08/01/05

LAYOUT	R.A.W.	08/01/05
DRAWN	B.A.K.	08/01/05
REVIEWED	C.A.H.	04/27/06

HANSON

Hanson Professional Services Inc.
3125 Dandy Trail, Suite 100
Indianapolis, Indiana 46214
Offices Nationwide

OVERLAY TAXIWAYS AND APRON

SUMMARY OF QUANTITIES, INDEX TO SHEETS

I:\AIRPORTS\KEWANEE\810-06TXYD\AIRPORT\SHEETS-SPLIT\R-002FLP.DWG - Model