

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE URBAN I000-2A			
20800150	TRENCH BACKFILL	CU YD	20	20			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	70	70			
40600300	AGGREGATE (PRIME COAT)	TON	320	320			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	10			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	750	750			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	380	380			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	840	840			
42001300	PROTECTIVE COAT	SQ YD	1354	1354			
44000125	BITUMINOUS REMOVAL OVER PATCHES 6 1/4"	SQ YD	2392	2392			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3890	3890			
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	3000	3000			
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	1500	1500			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1687	1687			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	405	405			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	300	300			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	85	85			
55039700	STORM SEWERS TO BE CLEANED	FOOT	2000	2000			
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2	2			
60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	24	24			
<del>60252000</del>	<del>CATCH BASINS TO BE RECONSTRUCTED</del>	<del>EACH</del>	<del>1</del>	<del>1</del>			
<del>60255500</del>	<del>MANHOLES TO BE ADJUSTED</del>	<del>EACH</del>	<del>2</del>	<del>2</del>			
<del>60257000</del>	<del>MANHOLES TO BE RECONSTRUCTED</del>	<del>EACH</del>	<del>2</del>	<del>2</del>			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	34	34			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	126	126			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE URBAN I000-2A			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18900	18900			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	848	848			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37700	37700			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4050	4050			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4150	4150			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1330	1330			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6300	6300			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	848	848			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37700	37700			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4050	4050			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4150	4150			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1330	1330			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1400	1400			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1400	1400			
* 81400215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	2	2			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3300	3300			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	257	257			
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	106	106			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	460	460			

\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES ARLINGTON HEIGHTS ROAD
NAME	DATE	