

IDOT CODE NO.	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY								UTILITY ADJUSTMENT Y060		STRUCTURES				LIGHTING Y030-1E	SIGNING Y002-1C
				100% STATE	50% STATE 50% BUFFALO GROVE	50% STATE 50% LONG GROVE	50% STATE 50% LINCOLN-SHIRE	50% STATE 50% CHARLES FIORE CO.	100% BUFFALO GROVE	100% LINCOLN-SHIRE	X928-2A		X028-2A						
											100% STATE	100% STATE	IL 22 OVER PEDESTRIAN TUNNEL	IL 22 OVER PED. TUNNEL EXTENSION	IL 22 OVER KILDEER CREEK	IL 22 OVER INDIAN CREEK			
				J000-2A	SFTY-1B	SFTY-1B	SFTY-1B	I000-1A	Y007	Y007									
• MX830110	LIGHT POLE, STEEL, 10.5M M.H., 2-1.8M MAST ARMS	EACH	4															4	
• MX830111	LIGHT POLE, STEEL, 12.2M M.H., 2-1.8M MAST ARMS	EACH	4															4	
• M8360100	LIGHT POLE FOUNDATION, 600MM DIAMETER	METER	240															240	
• 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	57															57	
• 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	20															20	
• XX004047	LIGHTING CONTROLLER SPECIAL	EACH	2															2	
• 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2															2	
• 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1															1	
• M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	9939	5177														4762	
• 84200700	LIGHTING FOUNDATION REMOVAL	EACH	22															22	
• 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	18															18	
• 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	4															4	
• X0324637	BASE COVER, LIGHT POLE	EACH	18															18	
• X0324223	MAINTENANCE OF LIGHTING SYSTEM	L SUM	1															1	
• X8380083	BREAKAWAY DEVICE	EACH	18															18	
MX030114	TRENCH DRAIN	METER	8												8				
MX030242	SLEEPER SLAB	METER	1422	1422															
MX032134	BRACED EXCAVATION	CU M	80											80					
MX032529	SEGMENTAL CONCRETE BLOCK WALL	SQ M	340	126															
MX033518	SEGMENTAL CONCRETE BLOCK WALL (SPECIAL)	SQ M	178										178						
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	23	23															
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	220	220															
X0323782	VORTEX MANHOLE, LOCATION NO. 1	EACH	1	1															
X0323783	VORTEX MANHOLE, LOCATION NO. 2	EACH	1	1															
X0323784	VORTEX MANHOLE, LOCATION NO. 3	EACH	1	1															
MX030199	TEMPORARY PAVEMENT	SQ M	11615	11615															
MX033519	TEMPORARY PATCHING	M TON	140	140															
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	9	9															
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	23	23															
X4023000	TEMPORARY ACCESS (ROAD)	EACH	28	28															
MX406M20	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	M TON	191	191															
MZ001050	AGGREGATE SUBGRADE 300MM	SQ M	120,004	119,643					361										
Z0002600	BAR SPLICERS	EACH	195										64		55		76		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1															
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	12	12															
Z0024478	FLEXIBLE DELINEATORS	EACH	35	35															
MZ050100	REMOVE AND RE-ERECT EXISTING HANDRAIL	METER	25												25				
MZ067300	STEEL CASING, 300MM	METER	14																
MZ067900	STEEL CASING, 600MM	METER	19																

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
NOTE BOOK		
AREAS CHECKED		
NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
NOTE BOOK		
AREAS CHECKED		
NO.		

• INDICATES SPECIALTY ITEMS

☐ INCLUDES Y031 IF TOTALS FROM PAGE 13

Rev. 6-2-05 Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 IL RTE 22 (FAP 337)
 IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)
SUMMARY OF QUANTITIES
 SHEET 8 OF 8
 SCALE: NONE DRAWN BY: JSM
 DATE: 03-22-2004 CHECKED BY: JNR