F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3537	5Y-R-4	DUPAGE	392	4

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

CONTRACT NO.62295

CODE	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY & DRAINAGE 80% FED. 20% STATE J000-2A	BRIDGE 80% FED. 20% STATE X028-2A	SIDEWALK 50% STATE 50% VILLAGE SFTY-1B	SIDEWALK 100% VILLAGE SFTY-1B	TRAFFIC SIGNALS US 20 @ MARCUS CINEMA DR 100% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ LOMBARD RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ ITASCA RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ MILL RD 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS US 20 @ JFK DR 80% FED 10% STATE 10% VILLAGE Y031-1F	TRAFFIC SIGNALS 100% VILLAGE Y031-1F	TRAFFIC SIGNALS INTERCONNECT ECONOLITE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS INTERCONNECT EAGLE 80% FED 20% STATE Y031-1F	TRAFFIC SIGNALS EVP EQUIPMENT 100% VILLAGE Y031-3D	RETAINING WALL 100% STATE Y007	RETAINING WALL 100% VILLAGE Y007	WATER MAIN 80% FED 20% STATE Y060	WATER MAIN 100% VILLAGE Y060	WATER MAIN 100% DUPAGE WATER COMMISSION Y060	WATER MAIN 50% VILLAGE 50% DUPAGE Y060	LIGHTING 100% VILLAGE Y030-1E
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	330	330																		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	345	345																		
20101100	TREE TRUNK PROTECTION	EACH	14	14																		
20200100	EARTH EXCAVATION	CU YD	28,028	28,028																		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,231	2,231																		
~~20400800~~	~~FURNISHED EXCAVATION~~	~~CU YD~~	~~10,556~~	~~10,556~~																		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	643	643																		
20800150	TRENCH BACKFILL	CU YD	20,987	12,333															8,654			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	31,574	31,574																		
21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	2,378	2,378																		
25000210	SEEDING, CLASS 2A	ACRE	7.00	7.00																		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	632	632																		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	632	632																		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	632	632																		
25100105	MULCH, METHOD I	ACRE	5.50	5.50																		
25100630	EROSION CONTROL BLANKET	SQ YD	33,952	33,952																		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3,760	3,760																		
28000300	TEMPORARY DITCH CHECKS	EACH	20	20																		
28100107	STONE RIPRAP CLASS A4	SQ YD	404	286	118																	
28200200	FILTER FABRIC	SQ YD	404	286	118																	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	13,649	13,649																		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.9	0.9																		
40600300	AGGREGATE (PRIME COAT)	TON	5	5																		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	120	120																		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	323	323																		
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9¾" (JOINTED)	SQ YD	100,596	100,596																		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	120	120																		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	7,916	7,916																		

VILLAGE= VILLAGE OF ADDISON
* SPECIALITY ITEM
△ Y080
□ STY-3N

SHEET 1 OF 11

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

US ROUTE 20 (LAKE STREET)

DATE: 03/01/05

DRAWN BY: SR
CHECKED BY: BSS

jwl_dot\171484_us20\cad\1484qq801-1b.sht